

MAR 02 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

For corners in

<u>Gogebic</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T48NR 46W	J-7
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Received for record the
22nd day of SEPTEMBER
 A. D. 1999 at 1:00 o'clock
P m., and recorded in
 Liber 7 of CORNER
 on page 251
Ramona Collins, Deputy
 Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Quarter Corner, Sections 14 & 23, T48N-R46W

I, John P. Goss, in a field survey on Aug. 29 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L
1											
2	6		5		4		3		2		1
3											
4	7		8		9		10		11		12
5											
6	18		17		16		15		14		13
7											
8	19		20		21		22		23		24
9											
10	30		29		28		27		26		25
11											
12	31		32		33		34		35		36
13											

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt, on May 27, 1851.

Original BT's. Y. Birch 14" S 62° W 21 links (13.86')
 Sugar 14" N 31° E 6 links (3.96')

Richard L. Drahn, 21564, on August 22, 1984, restored corner at record bearing and distance from the remains of the two original bearing trees. He set a 2" by 30" aluminum monument with 3/4" aluminum cap stamped to indicated the corner position. He established the following reference objects: 7" S. Maple N 65° W 34.73 ft.; 9" White Ash N 16° E 37.87 ft.; 13" S. Maple S 40° E 39.89 ft.; 6 ft. steel sign post S 180° W 1.9 ft.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

He recorded said corner in Liber 2, page 713 of Land Corners.

No original evidence found

Found Richard L. Drahn, monument and accessories.

Act 74 research on file.

DEER GROUP APPROVED
Richard L. Drahn 9/21/99
 COUNTY REGISTRATION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

From the found monument I established the following new and existing reference objects:

9" Sugar Maple	N 65° W	34.73 ft.	
11" White Ash	N 16° E	37.87 ft.	
16" Sugar Maple	S 40° E	39.93 ft.	new nail
5" Tw. Maple	N 43° E	8.76 ft.	
6' steel sign post	S 180° W	1.9 ft.	to face

(All distance taken to nail in side of tree)

Signed by John P. Goss
 Surveyor's Michigan License No. 23509

Date August 29, 1999

U.S.F.S. No. N-19

