

MAR 02 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office } ss.  
Gogebic County }

For corners in

Gogebic  
(County)

Located In:

Corner Code #

1. Public Land Survey

T48N R46W J-11  
T R  
T R  
T R  
T R

2. Property Controlling in Section

S T R  
S T R  
S T R  
S T R

3. Miscellaneous Property in Sec.

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

1/4 corner comm. to sec's. 26 & 35, T48N, R46W

I, John P. Goss, in a field survey on April 22, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

|    |    |   |    |   |    |   |    |   |    |   |    |
|----|----|---|----|---|----|---|----|---|----|---|----|
| A  | B  | C | D  | E | F  | G | H  | I | J  | K | L  |
| 1  |    |   |    |   |    |   |    |   |    |   |    |
| 2  | 6  |   | 5  |   | 4  |   | 3  |   | 2  |   | 1  |
| 3  |    |   |    |   |    |   |    |   |    |   |    |
| 4  | 7  |   | 8  |   | 9  |   | 10 |   | 11 |   | 12 |
| 5  |    |   |    |   |    |   |    |   |    |   |    |
| 6  | 18 |   | 17 |   | 16 |   | 15 |   | 14 |   | 13 |
| 7  |    |   |    |   |    |   |    |   |    |   |    |
| 8  | 19 |   | 20 |   | 21 |   | 22 |   | 23 |   | 24 |
| 9  |    |   |    |   |    |   |    |   |    |   |    |
| 10 | 30 |   | 29 |   | 28 |   | 27 |   | 26 |   | 25 |
| 11 |    |   |    |   |    |   |    |   |    |   |    |
| 12 | 31 |   | 32 |   | 33 |   | 34 |   | 35 |   | 36 |
| 13 |    |   |    |   |    |   |    |   |    |   |    |

Register of Deeds Stamp & File Number

Received for record the  
12<sup>th</sup> day of MAY  
A. D. 1999 at 10:20 o'clock  
A m., and recorded in  
7 of CORNER  
on page 149  
Ramona Collins Deput  
Register of Deeds

A. Description of original monument and accessories and/or subsequent restoration:  
Corner established by Austin Burt, U.S. Deputy Surveyor, on May 29, 1851.  
Original bearing trees: Hemlock 18" S 57° W 15 links (9.90')  
Hemlock 14" N 69° E 14 links (9.24')  
On August 22, 1984, Richard L. Drahn, RLS, USFS, restored corner position at record bearing and distance from the remains of the two original bearing trees. He set a 2" aluminum monument with 3/4" cap. He established the following reference objects: 9" S. Maple - N 37° W - 29.47'  
8" S. Maple - N 48° E - 11.98'; 7" Y. Birch - S 11° E - 19.52'  
6' steel sign post - S 85° E - 2.4'. Cap on monument indicate corner position.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
He recorded said corner in Liber 2, page 685 of Land corners for Gogebic County.  
Found Richard L. Drahn monument and reference objects.  
I updated the monument and accessories as noted below to state and county specification.  
Act 74 research on file.

Richard L. Drahn 5/11/99  
COUNTY \_\_\_\_\_

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
From found monument I established the following existing and new reference objects:

11" Sugar Maple N 37° W 29.47 ft.  
10" Sugar Maple N 44° E 11.98 ft.  
8" Yellow Birch S 11° E 19.52 ft.  
8" Hemlock S 75° W 4.92 ft.  
6' steel sign post S 85° E 2.4 ft. to face

( All measurement to nail in side of tree )

Signed by John P. Goss  
Surveyor's Michigan License No. 23509

Date April 28, 1999

U.S.F.S. No. V-19

