

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }  
Gogebic County } ss.

For corners in

Gogebic  
(County)

Located In: Corner Code ##

- 1. Public Land Survey T 47N R 46W J-1  
T R  
T R
- 2. Property Controlling S T R  
in Section S T R
- 3. Miscellaneous S T R  
Property in Sec. S T R

48N R 46W. J-13

Received for record the  
30<sup>TH</sup> day of DECEMBER  
A. D. 1993 at 12:20 o'clock  
P m., and recorded in  
Liber 4 of CORDERS

on page 326  
Betty Sosni, Deputy  
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

One-quarter corner common to S-2 & S-35, T47N, T48N, R46W.

I, John R. Garske, in a field survey on December 27, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

Survey by William A. Burt on September 9, 1847. Set sugar post from which a 16" sugar bears - N15°E - 18 links and a 16" sugar bears N87°W - 13 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence found. The corner position is marked by a found 6" spike at the center line/center line intersection of Stone Road and an old road to north. This corner position is currently in a harmonious location with occupation lines and is generally accepted as the corner by local residents. It has been used in several surveys of record and, as such, I am accepting it as the most probable location of the true one-quarter corner.

PEER GROUP APPROVED  
Richard R. Deahn 4/6/95  
COUNTY REPRESENTATIVE



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set large P.K. nail at corner position. Established the following bearing trees and reference objects:

- 5" basswood - N32°E - 35.66 feet
- 5" sugar - N51°W - 44.51 feet
- Reference monument - S44°E - 46.95 feet. Set 2 1/2" x 30" aluminum County Monument with a 3 1/2" stamped aluminum cap - steel sign post - 1.12 feet.
- Reference monument - S45°W - 49.35 feet. Set 2 1/2" x 30" aluminum County Monument with a 3 1/2" stamped aluminum cap - steel sign post - 1.37 feet.

Signed by John R. Garske Date 12/29/93  
Surveyor's Michigan License No. 28410