

MAR 02 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } sa.

Received for record the
22nd day of OCTOBER
A. D. 1999 at 1:40 o'clock
P m., and recorded in
Liber 7 of CORNERS
on page 260
Kamona Collins Deputy
Register of Deeds

Register of Deeds Stamp & File Number

For corners in
Gogebic
(County)
Located In: Corner Code #
1. Public Land Survey T48N R 46W K-6
T R
T R
T R
2. Property Controlling S T R
in Section S T R
3. Miscellaneous S T R
Property in Sec. S T R

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____
Quaret Section 13 & 14, T48N, R46W

I, John P. Goss, in a field survey on Sept. 28 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:
Corner established by Austin Burt, on May 26, 1851.
Original bearing trees: Spruce 12" S 72° W 35 links (23.10 ft.)
Y. Birch 8" N 74° E 16 links (10.56 ft.)
Richard L. Drahn, 21564, restored corner position at record bearing and distance from the windthrow stump hole of the original yellow birch bearing tree and other record natural features and line tree. He set a 2" iron pipe with 3" brass tablet stamped to indicated corner position. He established the following reference objects: 4" R. Maple-N51°W-15.84 ft.; 6" S. Maple-N80°E-15.30 ft.; 6" B. Ash-S40°E-23.58 ft.; 6' metal sign post-N39°W-1.3 ft.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
He recorded said corner in Liber 2, page 687 of Land Corners, on 12-06-84

No order evidence found

Found Richard L. Drahn, monument and accessories.

Act 74 research on file.

R. Drahn restored corner on July 24, 1984.

PEER GROUP APPROVED
Richard L. Drahn 10/14/99
COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
From the found monument I established the following new and existing reference objects:

6" Red Maple N 51° W 15.92 ft. new nail
6" Sugar Maple N 80° E 15.30 ft.
7" Black Ash S 40° E 23.58 ft.
4" Yellow Birch S 80° W 14.81 ft.
6' metal sign post N 39° W 1.25 ft. to face
(Measurement to nail in side of trees)



Signed by John P. Goss
Surveyor's Michigan License No. 23509
USFS L-21

Date Sept. 28, 1999