

MAR 02 2000

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Register's office }  
Gogebic County } ss.

SECTION

Received for record the  
21<sup>ST</sup> day of JULY  
A. D. 1999 at 1:25 o'clock  
P. m., and recorded in  
Liber 7 of CORNER  
on page 210  
Ramona Collins Dupitt  
Register of Deeds

For corners in

Gogebic  
(County)

Located in:

Corner Code #

1. Public Land Survey

T48N R46W K-8

2. Property Controlling  
in Section

S      T      R     

3. Miscellaneous  
Property in Sec.

S      T      R       
S      T      R     

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

Quarter Corner, Sections 23 & 24, T48N, R46W

I, John P. Goss, in a field survey on June 28 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L
2		6		5		4		3		2		1
3												
4		7		8		9		10		11		12
5												
6		18		17		16		15		14		13
7												
8		19		20		21		22		23		24
9												
10		30		29		28		27		26		25
11												
12		31		32		33		34		35		36
13												

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt, on May 24, 1851.

Original bearing trees: Cedar 12" S 56° E 9 links (5.94 ft.)  
B. Ash 10" N 69° W 8 links (5.28 ft.)

On July 12, 1984, Richard L. Drahn, RLS, restored corner position at record bearing and distance from the Ash bearing tree. He set a 3/4" aluminum rod monument with 3/4" aluminum cap, stamped to indicated the corner position. He established the following reference objects: 9" B. Ash N 28° W 24.31'; 11" Cedar N 60° E 25.70'; 6" Cedar S 65° W 10.25'; 6' steel sign post S 03° E 1.3'. He recorded said corner in Liber 2, Page 691 of Land Corners.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
No original evidence found

Found Richard L. Drahn monument and accessories.

Act 74 research on file.

DEED GROUP APPROVED  
Richard L. Drahn 7/20/99  
COUNTY REGISTER

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
From the found monument I established the following new and existing reference objects:

10" Black Ash (dead)	N 28° W	24.31 ft.
14" Cedar	N 60° E	25.68 ft. new nail
10" Cedar	S 65° W	10.41 ft. new nail
7" Ash	Due S.	16.31 ft.
6' steel sign post	S 03° E	1.0 ft. to face

(All measurement to nail in side of tree)



Signed by John P. Goss  
Surveyor's Michigan License No. 23509

Date June 28, 1999

U.S.F.S. No. P-21