

MAR 02 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } SS.

For corners in

Gogebic
(County)

Located In:

Corner Code #

- 1. Public Land Survey T48^N R 46^W K-10
T ___ R ___
T ___ R ___
T ___ R ___
- 2. Property Controlling in Section S ___ T ___ R ___
S ___ T ___ R ___
- 3. Miscellaneous Property in Sec. S ___ T ___ R ___
S ___ T ___ R ___

Received for record the
12TH day of MAY
A. D. 1999 at 10:20 o'clock
A m., and recorded in
Liber 7 of CORNERS
on page 150
Raymond Collins, Deputy
Register of Deeds

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

Quarter Corner, Sections 25 & 26, T48N, R46W

I, John P. Goss, in a field survey on April 29, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L
1											
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt, U.S. Deputy Surveyor, on May 24, 1851.
Original bearing trees: Cedar 10" S 57° W 18 links (11.88')
Sugar 10" N 69° E 25 links (16.50')

On August 14, 1984, Richard L. Drahn, RLS, restored corner position at record bearing and distance from the remains of the two original bearing trees. He set a 2" aluminum monument with 3/4" aluminum cap, stamped to indicate corner position. He established the following reference objects:
8" S. Maple - N 18° W - 22.50 ft.; 5" S. Maple - N 70° E - 16.67 ft.;
8" S. Maple - S 46° W - 19.29 ft.; 6' steel sign post - S 85° W - 1.2 ft.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

He recorded said corner in Liber 2, page 695 of Land Corners for Gogebic Co.
Found Richard L. Drahn monument and reference objects.
I updated the monument and accessories as noted below to state and county specification.

Act 74 research on file.

DEED GROUP APPROVAL
Richard L. Drahn 5/11/99
COUNTY ~~REGISTERED~~

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

From the found monument I established the following existing and new reference objects:

- 10" Sugar Maple N 12° W 22.50 ft.
- 7" Sugar Maple N 70° E 16.76 ft.
- 10" Sugar Maple S 46° W 19.04 ft. new nail
- 8" Sugar Maple S 80° E 14.88 ft.
- 6' steel sign post S 85° W 0.9 ft. to face

(All measurement to nail in side of tree)



Signed by John P. Goss
Surveyor's Michigan License No. 23509

Date April 29, 1999

U.S.F.S. No. T-21