

Register's Office }  
Gogebic County } ss.

Received for record the  
14<sup>TH</sup> day of AUGUST  
A. D. 1995 at 10:10 o'clock  
A m., and recorded in  
Liber 5 of CORNERS  
on page 286  
Ramona Collins Deputy  
Register of Deeds

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
Gogebic

(County)

Located in: Corner Code #

1. Public Land Survey T 47N R 46W K-1  
T 48N R 46 K-13  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

Sec. cor. comm. to Sec's. 1 & 2, T.47 N., R.46W  
and 35 & 36, T.48 N., R.46 W.

I, John P. Goss in a field survey on July 30, 1995  
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned  
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the  
current manual of survey instructions of the United States Department of the Interior, Bureau of Land  
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5  
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a  
Court of Law; established, re-established, monumented, re-monumented, recovered, found as  
expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded  
on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	16		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by William A. Burt. Set sugar post.  
Original bearing trees: Hemlock 16" N 65° E 52 links  
Hemlock 20" N 27° W 28 links

John R. Garske re-established this corner in 1991. He recorded it in  
Liber 4 page 51 of Land Corners for Gogebic County. He established the  
following witnesses and distances. 6" Maple- S 54° W- 90.45'; 14" Maple  
S 75° E- 111.45'; 14" Maple S 41° E- 104.42. He set a 3/4 inch diameter  
by 4 foot long iron rod with plastic cap at the Section corner location.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I did not find the 3/4" by 4' iron rod. I found the three (3) witnesses  
trees, which checked out to one location. I updated the Corner monument and  
accessories as noted below to state and county specification.

Act 74 reseach on file with the County Register of Deeds Office.

Richard L. Duda 8/9/95  
COUNTY REGISTER

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I set a 2 1/2" by 30" aluminum pipe with a 3 1/2" aluminum cap stamped as follows  
at location of corner: County Remonumentation; T.47-48 N, R.46 W.;  
S-1, S-2, S-35 and S-36; 1995, P.S. 23509. I established the following  
bearing trees and reference objects.

7" Maple S 54° W 90.45'  
14" Maple S 75° E 111.45'  
16" Basswood S 41° E 104.42'  
26" Hemlock N 58° W 124.45'



Signed by John P. Goss Date July 31, 1995

Surveyor's Michigan License No. P.S. 23509

Fed. No. A-21

2. 42