

MAR 02 2000

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

For corners in SECTION

Gogebic
(County)

Located In:

Corner Code #

1. Public Land Survey

T48N R46W

L-5

T R

T R

T R

2. Property Controlling
in Section

S T R

S T R

3. Miscellaneous
Property in Sec.

S T R

S T R

Received for record the
21ST day of JULY
A. D. 1999 at 1:25⁰ clock
P. M., and recorded in
Liber 7 of CORNERS
on page 212
Barbara Collins, Deputy
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Quarter Corner, Section 12 & 13, T48N, R46W

I, John P. Goss, in a field survey on June 29, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	10		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt, on May 26, 1851.

Original bearing trees: Y. Birch 14" S 40° W 24 links (15.84 ft.)
Y. Birch 16" N 67° E 6 links (3.96 ft.)

On July 24, 1984, Richard L. Drahn, RLS, restored corner position at record distance and bearing from the remains of the two original bearing trees. He set a 2" aluminum monument with 3/4" aluminum cap, stamped to indicated the corner position. He established the following reference objects:

11" White Ash N 75° W 11.72 ft.; 10" Sugar Maple N 67° E 20.26 ft.;
6' steel sign post N 40° W 1.5 ft.; 9" Y. Birch S 09° E 51.69 ft.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

He recorded said corner in Liber 2, page 701 of Land Corners.

No original evidence found.

Found Richard L. Drahn monument and accessories.

Act 74 research on file.

FIELD GROUP APPROVED
Richard L. Drahn 7/20/99
COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
From the found monument I established the following new and existing reference objects:

15" White Ash N 75° W 11.79 ft. new nail
13" Sugar Maple S 67° E 20.26 ft.
11" Yellow Birch S 09° E 51.65 ft.
8" Maple S 24° W 27.00 ft.
6' steel sign post N 40° W 1.5 ft. to face

(All measurement to nail in side of tree)



Signed by John P. Goss
Surveyor's Michigan License No. 23509

Date June 29, 1999

U.S.F.S. No. J-23