

MAR 02 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Gogebic

(County)

Located In:

Corner Code #

1. Public Land Survey

T48<sup>N</sup>R46<sup>W</sup>

L-9

T R

T R

T R

2. Property Controlling  
in Section

S T R

S T R

3. Miscellaneous  
Property in Sec.

S T R

S T R

Register's Office }  
Gogebic County }

Received for record the  
21<sup>ST</sup> day of JULY  
A. D. 1999 at 1:35 o'clock  
P m., and recorded in  
Liber 7 of CORNERS  
on page 215  
Ramona Collins Dwyer  
Register of Deeds  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

1/4 corner, Section 24 & 25, T48N, R46W

I, John P. Goss, in a field survey on June 18, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	I
1													
2	6			5			4			3			2
3													
4	7			8			9			10			11
5													
6	18			17			16			15			14
7													
8	19			20			21			22			23
9													
10	30			29			28			27			26
11													
12	31			32			33			34			35
13													

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt on May 24, 1851.

Original bearing trees: Hemlock 30" S 65° W 12 links (7.92 ft.)  
Hemlock 12" N 68° E 9 links (5.94 ft.)

On July 2, 1984, Richard L. Drahn, RLS, restored corner position at record bearing and distance from the remains of the two original bearing trees.

He set a 2" by 30" aluminum monument with 3/4" aluminum cap, stamped to indicate the corner position. He established the following reference objects:  
8" Sugar Maple N 41° W 9.60 ft.; 6" Sugar N 18° E 15.40 ft.;  
14" Sugar Maple S 33° E 22.56 Ft.; 6' steel sign post S 22° E 1.8 ft.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

He recorded said corner in Liber 22, page 705 of Land Corners for Gogebic Co.

Found the Northeast original bearing tree, now a very badly decayed 12"-18" Hemlock stump.

Found Richard L. Drahn monument and accessories.

Act 74 research on file.

DEED GROUP APPROVED  
Richard L. Drahn 7/20/99  
COUNTY PROFESSIONAL SURVEYOR

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

From found monument I established the following new and existing reference objects:

10" Sugar Maple N 41° W 9.60 ft.  
9" Sugar Maple N 18° E 15.40 ft.  
19" Sugar Maple S 33° E 22.56 ft.  
11" Sugar Maple S 36° W 32.28 ft.  
6' Steel sign post S 22° E 1.8 ft. to face

(All measurement to nail in side of tree)



Signed by John P. Goss

Date June 18, 1999

Surveyor's Michigan License No. 23509

U.S.F.S. No. R-23