

MAR 02 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's office }
Gogebic County } ss.

For corners in

<u>Gogebic</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>48N</u> R <u>45W</u>	<u>A-2</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	<u>M-2</u>
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Received for record the
26TH day of AUGUST
A. D. 1999 at 1:40 o'clock
P M., and recorded in
Lib. 7 of CORNERS
on page 227
Ramona Collins Deputy
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

1/4 CORNER 6 & 1, T. 48N., R. 45-46W.

I, Richard L. Drahn, in a field survey on August 22, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by John Burt on 9/10/1847. Original bearing trees:

Sugar	10"	S.10° W.	25 links	(16.50')
Y. Birch	16"	N.35° E.	30 links	(19.80')

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I restored the corner position at record bearing and distance from the remains of the two original bearing trees. The first is a large windthrown stump hole. The second one is now a large series of root holes with fragments of Yellow Birch bark. Distance checks to recovered corners 40.00 chains north and south, and 39.88 chains south.

A 3/4" X 2' iron pipe set by Gogebic County Forestry Commission bears N.02° W., 2.4' from the original corner location.

Corner research on file with Gogebic County records.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 2" x 30" aluminum pipe monument with a 3 1/4" stamped aluminum cap and the following new B.T.s (all measurements taken to a nail in side of tree):

Sugar Maple	9'	N.60° E.	33.07'
Basswood	13"	S.05° W.	22.32'
Sugar Maple	6"	S.72° W.	27.98'
Steel sign rail	6'	N.40° W.	2.07'

BEER GROUP APPROVED
Richard L. Drahn 8/24/99
COUNTY REPRESENTATIVE



Signed by Richard L. Drahn Date August 23, 1999
Surveyor's Michigan License No. 21564