

SURVEY & REMONUMENTATION

SEP 08 1998

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **SECTION**

<u>Gogebic</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>48N</u> R <u>45W</u>	<u>A-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T <u>48N</u> R <u>46W</u>	<u>M-7</u>
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register's Office } ss.
Gogebic County }

Received for record the
23RD day of JULY

A. D. 1998 at 11:40 o'clock

A m., and recorded in

Liber 7 of CORNERS

on page 32
Ramona Collins, Deputy
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Section Corner 18, 19, 13 & 24; T.48 N., R.45-46 W.

I, Richard L. Drahn in a field survey on July 8, _____, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by John Burt on 9/10/1847. Original B.T.s --- Sugar 20" S.80 E. 14 links (9.24') --- Y. Birch 20" N.65 W. 22 links (14.52') --- David Barnhart on 4/10/35 recovered a scribed 14" witness tree at this location. He placed a location poster on a 12" Sugar Maple. Corner restored by Richard L. Drahn (21564) on 7/30/84 from the remains of the two original B.T.s. He set a 2" X 5' iron pipe with a 3" stamped brass cap and the following new bearing trees.

10"	Sugar Maple	S.89 W.	12.63'
12"	Red Maple	N.20 E.	11.44'
8"	Sugar Maple	S.70 E.	11.31'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

6' Steel sign rail N.32 W. 1.7'

Corner recorded in Gogebic County Liber 2, Page 709 on 12/10/84.

Corner research on file with Gogebic County records.

Recovered the monument as described and the bearing trees as follows:

11"	dead Sugar Maple	N.87 W.	12.61'
15"	Red Maple	N.21 E.	11.57' (new nail)
9"	Sugar Maple	S.78 E.	11.30'
6'	Steel sign rail	N.31 W.	1.69'

Stump holes are all that remain of the original bearing trees.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

New bearing tree referenced:

10" Red Maple S.50 W. 6.02'

Resource grade GPS Lat. 46-32-58.06 N
Long. 89-59-22.84 W

PEER GROUP APPROVAL

Richard L. Drahn 7/22/98
COUNTY REPRESENTATIVE



Signed by Richard L. Drahn Date July 19, 1998

Surveyor's Michigan License No. 21564