

SURVEY & REMONUMENTATION

SEP 08 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Gogebic (County) Located In: Corner Code #

1. Public Land Survey T 48NR 45W A-8
T _____ R _____
T _____ R _____
T 48NR 46W M-8

2. Property Controlling in Section S T R _____
S _____ T _____ R _____

3. Miscellaneous Property in Sec. S _____ T _____ R _____
S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Register's Office } ss.
Gogebic County }

Received for record the 23RD day of JULY A. D. 1998 at 11:40 o'clock P m., and recorded in Liber 7 of CORNERS on page 33
Ramona Collins, Deputy
Register of Deeds

Register of Deeds Stamp & File Number

1/4 Corner 19 & 24; T.48 N., R.45-46 W.

Richard L. Drahn, in a field survey on July 8, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by John Burt on 9/10/1847. Original B.T.s --- Sugar 10" S.45 W. 24 links (15.84') --- Sugar 16" N.25 E. 50 links (33.00') --- Corner position restored by Richard L. Drahn (21564) on 8/15/84 from the stump holes of the two original B.T.s and from distances north and south to recovered line trees, natural features and section corners. He set a 2" X 30" aluminum pipe with a 3 1/4" stamped aluminum cap and the following:

14"	Yellow Birch	N.09 E.	22.45'
11"	Sugar Maple	S.59 E.	30.91'
10"	Red Maple	S.27 W.	29.37'
6'	Steel sign rail	East	1.65'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Corner recorded in Gogebic County Liber 2, Page 657 on 12/10/84.

Corner research on file with Gogebic County records.

Recovered the monument as described and the bearing trees as follows:

18"	Yellow Birch	N.07 E.	22.47'
13"	Sugar Maple	S.61 E.	30.88'
13"	Red Maple	S.24 W.	29.40' (new nail)
6'	Steel sign rail	East	1.66'

Only stump holes remain from the original B.T.s

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

New bearing tree referenced:

8"	Basswood	N.58 E.	44.85'
----	----------	---------	--------

Resource grade GPS Lat. 46-32-32.01 N
Long. 89-59-22.71 W

PEER GROUP APPROVAL

Richard L. Drahn 7/22/98
COUNTY REPRESENTATIVE



Signed by Richard L. Drahn Date July 19, 1998

Surveyor's Michigan License No. 21564