

**SURVEY & REMONUMENTATION**

OCT 03 1996

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }  
Gogebic County } ss.

Received for record the  
16<sup>TH</sup> day of AUGUST  
A. D. 1996 at 10:30 o'clock  
A m., and recorded in  
Liber 5 of CORNERS  
on page 403  
Ramona Collins Deputy  
Register of Deeds

For corners in  
Gogebic  
(County)

Located In:	Corner Code #
<u>T.48N R.47W</u>	<u>A-4</u>
<u>T.48N R.48W</u>	<u>M-4</u>
T _____ R _____	_____
T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____

- Public Land Survey
- Property Controlling in Section
- Miscellaneous Property in Sec.

Register of Deeds Stamp & File Number

- Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- Private Claims \_\_\_\_\_

1/4 corner to sec's 7 & 12; T.48 N., R.47-48 W.

I, John P. Goss, in a field survey on July 23, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therofore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
Original corner established by William Burt in 1847.  
Original bearing trees: Hemlock 9" S 73° E 27 links (17.82')  
Hemlock 12" S 23° W 39 links (25.74')  
Richard L. Drahn & John P. Goss, both R.L.S. restored the corner position at record bearing and distance from the remains of the original bearing trees. At the corner position they set a 1 1/2" I.D. by 4 foot long, concrete filled, iron pipe, capped with a 3" circular brass table which reads: T.48 N., R.47-48 W.; S-7, S-12; 1978; R.L.S. 23509. From which they established the following new blazed and scribed bearing trees:

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
10" Yellow Birch S 60° W 8.6' and recorded said corner in Liber 1 on  
8" Sugar Maple S 44° E 25.7' pages 406 and 407 of Land Corners for  
8" Sugar Maple N 13° E 21.4' Gogebic County.


Act 74 research on file.

I found the 1 1/2" I.D., iron pipe with 3" circular brass table and it checked with Drahn and Goss witnesses. I updated the accessories as noted below to state and county specification. All evidence found in 1978 survey still at this location.

PEER GROUP APPROVED  
Richard L. Drahn 8/18/96  
COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
From the 1 1/2" iron pipe with 3" brass table, I established the following existing and new bearing trees and reference objects.

15" Yellow Birch	S 60° W	8.63'
13" Sugar Maple	S 44° E	25.67'
13" Sugar Maple	N 13° E	21.38'
9" Sugar Maple	N 12° W	28.32'
6' rail & Sign	Due N	1.13'



Signed by John P. Goss Date July 24, 1996

Surveyor's Michigan License No. 23509

Fed No. G-1 & G-25