

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Gogebic Located In: Corner Code #  
 (County)

1. Public Land Survey T48N R 47W D - 3  
 T R  
 T R  
 T R SURVEY &  
 2. Property Controlling S T R MONUMENTATION  
 in Section S T R  
 3. Miscellaneous S T R  
 Property in Sec. S T R JAN 05 2001

Register's Office }  
 Gogebic County } 88.

Received for record the  
2<sup>ND</sup> day of JUNE  
 A. D. 1900 at 10:30 o'clock  
A m., and recorded in  
 Liber 7 of CORNERS

page 371  
*Chester Ruppel*  
 Register of Deeds  
 Register of Deeds Stamp & File Number

**SECTION**

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_  
 Quarter Corner common to Sections 5 & 8, T 48 N, R 47 W

I, John R. Garske, in a field survey on December 15, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

1	A	B	C	D	E	F	G	H	I	J	K	L
2		6		5		4		3		2		1
3				●								
4		7		8		9		10		11		12
5												
6		18		17		16		15		14		13
7												
8		19		20		21		22		23		24
9												
10		30		29		28		27		26		25
11												
12		31		32		33		34		35		36
13												

**A. Description of original monument and accessories and/or subsequent restoration:**

Original Survey: William Ives, P.S., in 1848  
 Original Corner: Wood Post  
 Original Bearing Trees: 8" Tamarack S 23° E 18 Links  
 10" Tamarack N 53° w 19 Links

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

No corner evidence found. Set point opposite of fenceline to South and on centerline of Lake Road.

Distance East 2654.45 feet and West 2649.81 feet check with this position.

Record research on file.

NEER GROUP APPROVED  
*Richard L. Dral* 5/24/00  
 COUNTY REGISTER

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

I set a stamped 5/8" iron rod with a stamped brass cap in the centerline of Lake Road and a Bernsten standard 2 1/2" x 42" aluminum monument as a reference monument. Also, established the following witnesses:

Reference monument	South	32.86 Feet
10" Maple	S 52° W	60.87 Feet
12" Cedar	N 28° W	47.18 Feet
6" Tamarack	N 50° E	51.42 Feet



Signed by *John R. Garske*  
 Surveyor's Michigan License No. 28410  
 Field Book # 239, Page 101