

SURVEY & REMONUMENTATION

OCT 0 3 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
 Gogebic County } ss.

Received for record the
28th day of MARCH
 A. D. 1996 at 11:25 o'clock
A m., and recorded in
 Liber 5 of CORNERS
 on page 341
Ramona Collins, Deputy
 Register of Deeds

For corners in Gogebic Located In: _____ Corner Code # _____
 (County)

1. Public Land Survey	T	48N	R	47W	E-11
	T	_____	R	_____	_____
	T	_____	R	_____	_____
	T	_____	R	_____	_____
2. Property Controlling In Section	S	_____	T	_____	R
	S	_____	T	_____	R
3. Miscellaneous Property in Section	S	_____	T	_____	R
	S	_____	T	_____	R

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Register of Deeds Stamp & File Number

Section corner common to Sections 28, 29, 32 & 33, T47N, R46W

I, John R. Garske, in a field survey on January 15, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	13		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- In 1848 William Ives, U.S. Deputy Surveyor, set a wooden post from which a 14" hemlock - bears N08°W - 11 links (7.26 feet) and a 15" sugar - S45°E - 34 links (22.44 feet).
- On Dec. 14, 1983, John R. Garske, RLS 28410, reestablished the corner position as recorded on February 8, 1984, in Liber 2 of Land Corners, on Page 563, the corner consisting of a P.K. nail at the centerline of Junet and Airport Roads from which the following reference objects were established: Fence post - N47°W - 60.92 feet, power pole - N39°E - 39.62 feet, power pole - S74°W - 128.25 feet.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found P.K. nail 1 1/2" below asphalt road surface and checked with the one available witness (power pole - N39°E - 39.62 feet) also checked with a distance south to the monumented section corner.

I updated the corner position to State and County specifications as noted below.

(P.A. 74 Research on File)

PEER GROUP APPROVED
Richard P. Dean 3/27/96
 COUNTY REPRESENTATIVE



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I replaced the found P.K. nail with a stamped brass cap from which I established the following reference objects:

- Power pole - N39°E - 39.62 feet (existing)
- Power pole - S54°W - 56.82 feet
- Cuy pole - N63°W - 56.57 feet
- Reference monument consisting of a 2 1/2" dia. x 30" long aluminum pipe with a 3 1/4" diameter aluminum cap stamped: County Remonumentation; T48N, R47W, S-29, S-28, S-32, S-33; 1996; RLS 28410; R.M., N45°W - 48.92 feet; set 6 foot steel rail with sign 0.90 feet away.

Signed by John R. Garske
 Surveyor's Michigan License No. 28410

Date 3/26/96