

SURVEY & REMONUMENTATION

OCT 03 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in	Gogebic	Located In:	Corner Code #
	(County)		
1. Public Land Survey	T 48N R 47W		E-12
	T _____ R _____		_____
	T _____ R _____		_____
	T _____ R _____		_____
2. Property Controlling in Section	S _____ T _____ R _____		_____
	S _____ T _____ R _____		_____
3. Miscellaneous Property in Section	S _____ T _____ R _____		_____
	S _____ T _____ R _____		_____

Register's Office }
 Gogebic County } ss.

Received for record the
28TH day of MARCH
 A. D. 1996 at 11:35 o'clock
A m., and recorded in
Liber 5 of CORNERS
on page 342
Ramona Mollum Deputy
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

One-quarter corner common to Sections 32 and 33, T48N, R47W.

I, John R. Garske, in a field survey on January 15, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- In 1848 William Ives, U.S. Deputy Surveyor, set a post from which a 14" lynn bears S46°W - 36 links (23.76 feet); and a 14" sugar - N28°E - 22 links (14.52 feet).
- On December 14, 1983, John R. Garske, RLS 28410, reestablished the corner position consisting of a P.K. nail from which a power pole bears N12°E - 62.58 feet; power pole - S85°W - 44.27 feet; and a P.K. nail - due north - 6.58 feet. Recorded Liber 2, Pg. 561 of Land Corners.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of the reestablished corner position from 1983 could be found due to road reconstruction. Reestablished the corner position at proportional distances between opposing section corners and monumented this position to State and County specifications as noted below.

(P.A. 74 Research on File)

PEER GROUP APPROVED
Richard P. Dahn 3/27/96
COUNTY REPRESENTATIVE



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

The corner position is marked by a P.K. nail in the centerline of Junet Road from which I established the following reference objects:

- Telephone Pole #M-78 - N12°E - 62.85 feet
- Power Pole #32-93/50 - S83°W - 44.56 feet
- Two reference monuments each consisting of a 2 1/2" dia. x 30" long aluminum pipe with a 3 1/4" dia. cap stamped: County Remonumentation; T48N, R47W; 1/4; R.M.; S-33; S-34; 1996; RLS 28410
- R.M. #1 - N83°E - 28.79 feet with 6' steel rail with sign 1.0 feet away
- R.M. #2 - S45°E - 44.18 feet with 6' steel rail with sign 1.0 feet away

SEE SKETCH ON BACK

Signed by John R. Garske Date 3-27-96
 Surveyor's Michigan License No. 28410

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983

SURVEY &
REMONUMENTATION

OCT 03 1996

COMMISSION

SKETCH
NO SCALE

