

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
 Gogebic County }

Received for record the
16TH day of SEPT
 A. D. 1994 at 3:50 o'clock
P m., and recorded in
 Liber 5 of CORNERS
 on page 102.
Romona Collins, Deputy
 Register of Deeds

Register of Deeds Stamp & File Number

For corners in

Gogebic
 (County)

Located In: Corner Code #

- | | | |
|------------------------------------|---------------------------|------|
| 1. Public Land Survey S-5 | T <u>47N</u> R <u>47W</u> | E-1 |
| | T _____ R _____ | |
| | T <u>48N</u> R <u>47W</u> | E-13 |
| | T _____ R _____ | |
| 2. Property Controlling in Section | S _____ T _____ R _____ | |
| | S _____ T _____ R _____ | |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | |
| | S _____ T _____ R _____ | |

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Section corner common to Sections 32 & 33, T48N, R47W
 and Sections 4 & 5, T47N, R47W

I, John R. Garske, in a field survey on July, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original survey by William A. Burt, D.S., in 1847. Set cedar post. Original bearing trees: Hemlock 10" - N08°E, 11 links; Spruce 14" - N59°W, 22 links. Trees set by William Ives, D.S. in 1848: Hemlock 12" - S62°E, 33 links; Fir 12" - S60°W, 45 links.

The corner was set by John R. Garske, RLS 28410 in 1983 consisting of a P.K. nail in the road intersection. Accessories: Guy pole - N44°W, 45.52 feet; P. pole - N45°E, 49.63 feet; Tele. pole - S40°W, 39.28 feet. *RECORDED 2/18/84; LIBER 2, PAGE 559*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I found a P.K. nail marking the corner position which checks with the witnesses in my previous certificate. I updated the corner as noted below to bring it up to county and state specifications.

Act 74 research on file with County Register of Deeds Office.

FEER GROUP

Approved

Richard L. Deahn

9/14/94



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I replaced the found P.K. nail with a 2 1/2" brass cap with a 2" stem set in anchoring cement recessed in the pavement at the corner position. Cap is stamped S-32, S-33, S-4, S-5, T48-47N, R47W, 1994, RLS 28410. I established the following reference objects: A reference monument consisting of a 2 1/2" x 30" aluminum pipe with a 3 1/4" aluminum cap stamped to indicate the corner position as follows: R.M. - Due West - 20 feet, with a steel sign post 0.92 feet away; Existing guy pole - N44°W, 45.52 feet; Existing P. pole - N45°E, 49.63 feet; Tele. pole - S40°W, 39.28 feet.

Signed by John R. Garske
 Surveyor's Michigan License No. 28410

Date 8/29/94