

SURVEY & REMONUMENTATION

OCT 03 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

Received for record the
10TH day of JUNE
A. D. 1996 at 9:30 o'clock
4 m., and recorded in
Liber 5 of CORNERS
page 350
Ramona Collins, Deputy
Register of Deeds

Register of Deeds Stamp & File Number

For corners in	Located In:	Corner Code #
Gogebic (County)		
1. Public Land Survey	T 48N R 47W	F-11
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

One-quarter corner common to Sections 28 and 33, T48N, R47W.

I, John R. Garske, in a field survey on January 22, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

On September 20, 1848, William Ives, U.S. Deputy Surveyor, set a post from which an 8" sugar bears N32°E - 19 links and a 12" sugar - S19°W - 25 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original corner evidence could be found due to logging activity, road and utility construction. I reestablished the corner position at proportional distances between opposing section corners at the centerline of Airport Road and monumented this position to state and county specifications as noted below. An old fence line and blue line extend south from the corner location.

(Record Research on File)

PEER GROUP APPROVED
Richard H. Drazin 6/6/96
COUNTY REPRESENTATIVE



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

The corner position is marked by a 3" diameter brass cap in the centerline of Airport Road. Brass cap is stamped: T48N, R47W; 1/4; S-28; S-33; 1996; R.L.S. 28410; from which I established the following bearing trees and/or reference objects:

- 5" B. Ash - N55°E - 64.78 feet
- 6" B. Ash - S35°E - 59.45 feet
- 14" Sugar - S51°W - 52.82 feet

Reference monument consisting of a 2 1/2" diameter x 30" long aluminum pipe with a 3 1/4" diameter aluminum cap stamped: County Remonumentation; T48N, R47W; R.M.; 1/4; S-28; S-33; 1996; R.L.S. 28410, S05°E - 23.19 feet; set 6 foot steel rail with sign 1.30 feet away.

Signed by John R. Garske Date 6/6/96
Surveyor's Michigan License No. 28410

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983