

SURVEY & REMONUMENTATION

JUN 29 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

_____ Gogebic _____ (County)	Located In:	Corner Code #
1. Public Land Survey S-15	T <u>48N</u> R <u>47W</u>	<u>G-6</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section S _____	T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous S _____	T _____ R _____	_____
Property in Sec. S _____	T _____ R _____	_____

Register's Office }
 Gogebic County } ss.

Received for record the
12th day of APRIL
 A. D. 1995 at 1:30 o'clock
P. m., and recorded in
 Liber 5 of CORNERS
 on page 240
Ramona Collins, Deputy
Register of Deeds
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

One quarter corner common to Sections 16 & 15, T48N, R47W

I, John R. Garske, in a field survey on March 29, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

On September 17, 1848, William Ives set a quarter section post from which a 10" sugar bears S32°W, 36 links and a 8" sugar - N40°E, 43 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I established the corner position by measurements from existing corners north and south and is positioned on the centerline of a N-S paved road at the extension of ancient fence lines running east and west.

Record research on file with Register of Deeds.

PEER GROUP APPROVED
Richard L. Duden 4/6/95
COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I set a 3 1/4" diameter brass cap stamped: T48N, R47W; 1/4; S-16; S-15; 1995; RLS 28410, from which I established the following bearing trees and reference objects: power pole - N24°E, 87.03 feet; 6" sugar - S51°W, 52.10 feet; 6" sugar - N35°W, 52.75 feet; a reference monument consisting of a 2 1/2" diameter x 30" long aluminum pipe with a 3 1/4" diameter aluminum cap stamped: County Remonumentation; T48N, R47W; R.M.; 1/4; S-16; S-15; 1995; RLS 28410; N89°W, 34.93 feet; 6 foot steel rail with sign - 1.27 feet away.



Signed by John R. Garske Date 4-6-95
 Surveyor's Michigan License No. 28410