

**SURVEY &
REMONUMENTATION**

FEB 18 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Gogebic
(County)

Located In:

Corner Code #/

- 1. Public Land Survey Section 34 T 48N R 47W
 T _____ R _____
 T _____ R _____
 T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

G-11

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

Section corner common to Sections 27, 28, 33 and 34, T48N, R47W.

December 20 93

I, John R. Garske, in a field survey on _____, 19 _____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original survey by William Ives, Deputy Surveyor, in 1848. Original corner set was a wooden post and original bearing trees are:

- Tamarack 8" - S32°W - 16 links (10.56 feet)
- Tamarack 10" - N41°E - 27 links (14.52 feet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found a P.K. nail at the centerline of Vanderhagen and Airport Roads, marking the corner position. This corner position has been used and accepted for over 30 years by several surveyors, local residents and the County Road Commission. Old fence lines along the road rights-of-way coincide with this corner position which has been used in several surveys of record.

I am accepting this corner position as the most probable location of the true corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set an 8" cotton spike (1/2" diameter hardened steel tapered to a point) at the found P.K. nail in the center line of the paved road intersection from which I established:

- Power Pole #28-97/05 - N54°W - 49.95 feet
- Power Pole #20 RRX - N55°E - 53.26 feet
- Reference monument - 3/4" x 48" aluminum rod with 3 1/2" diameter stamped aluminum cap - S48°W - 52.65 feet - steel sign post - 1.38 feet
- Reference monument - 3/4" x 48" aluminum rod with 3 1/2" diameter stamped aluminum cap - S47°E - 53.35 feet - steel sign post - 1.52 feet

Signed by John R. Garske
 Surveyor's Michigan License No. 28410

Date 12/23/93

Register's Office }
 Gogebic County } ss.

Received for record the
30th day of DECEMBER
 A. D. 1993 at 12:30 o'clock
P.m., and recorded in
 Liber 4 of CORNERS
 on page 337
Betty Lassie Deputy
 Register of Deeds

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	13	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

