

**SURVEY & REMONUMENTATION**

OCT 08 1996

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

Register's Office }  
 Gogebic County } ss.

For corners in	Located In:	Corner Code #
<u>Gogebic</u> (County)		
1. Public Land Survey	T 48N R 47W	G-12
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling In Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Received for record the  
20<sup>th</sup> day of MARCH  
 A. D. 1996 at 11:35 o'clock  
A m., and recorded in  
Liber 5 of CORNEAS  
 on page 343.

*Ramona Collins, Deputy*  
 Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

One-quarter corner common to Sections 33 and 34, T48N, R47W.

I, John R. Garske, in a field survey on January 15, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

On September 17, 1848, William Ives, U.S. Deputy Surveyor, set a post from which a 12" cedar bears S76°W - 12 links (7.92 feet) and a 14" cedar - N26°E - 14 links (9.24 feet).

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

No original evidence or subsequent restoration was found due to logging and farming activity and due to road and utility construction.

I reestablished the corner position on line and mid-way between the monumented section corner common to Sections 27, 28, 33 and 34, T48N, R47W and the section corner common to Sections 33 and 34, T48N, R47W and Sections 3 and 4, T47N, R47W.

I monumented the corner to State and County specifications as noted below.


(Record Research on File)

PEER GROUP APPROVED  
*Richard L. Dralun* 3/27/96  
 COUNTY REPRESENTATIVE

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

The corner position is marked by a 2 1/2" dia. x 30" long aluminum pipe with a 3 1/4" dia. aluminum cap stamped: County Remonumentation; T48N, R47W; 1/4; S-33; S-34; 1996; RLS 28410, from which I established the following bearing trees and reference objects:

- 5" cedar - N01°E - 43.35 feet
- 10" cherry - N17°E - 38.62 feet
- 8" cedar - S43°E - 13.50 feet
- 6' steel rail with sign - East - 1.30 feet



Signed by John R. Garske  
 Surveyor's Michigan License No. 28410

Date 3/27/96