

SURVEY & REMONUMENTATION

JUN 29 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
 Gogebic County } 98.

Received (or record) this
12th day of APRIL
A. D. 1995 at 1:30 o'clock
P. m., and recorded in
 Liber 5 of CORNERS
 on page 242
Ramona Collins, Deputy
 Register of Deeds

For corners in

<u>Gogebic</u> (County)	Located In:	Corner Code =#
1. Public Land Survey S-15	T <u>48N</u> R <u>47W</u> T 47N R 48W	H-5
2. Property Controlling in Section	S ___ T ___ R ___ S ___ T ___ R ___	___
3. Miscellaneous Property in Sec.	S ___ T ___ R ___ S ___ T ___ R ___	___

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____
 One quarter corner common to Sections 10 & 15, T48N, R47W

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, John R. Garske, in a field survey on March 29, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

On September 18, 1848, William Ives set a quarter section post from which a 12" sugar bears S11°E, 15 links and a 6" sugr - N53°W, 41 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I established the corner position by measurements from existing corners and is positioned on centerline of a paved road at the extension of ancient fence lines running north and south.

Record research on file with Register of Deeds.

PEER GROUP APPROVED
Richard L. Ordum 4/6/95
COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I set a 3 1/4" diameter brass cap stamped: T48N, R47W; 1/4; S-10; S-15; 1995; RLS 28410, from which I established the following bearing trees and reference objects: 6" basswood - N45°E, 47.19 feet; 16" sugar - S45°E, 70.05 feet; 10" R. pine - N41°W, 39.05 feet; a reference monument consisting of a 2 1/2" diameter x 30" long aluminum pipe with a 3 1/4" diameter aluminum cap stamped: County Remonumentation; T48N, R47W; R.M.; 1/4; S-10; S-15; 1995; RLS 28410; N29°E, 44.53 feet; 6 foot steel rail with sign - 1.70 feet away.

Signed by John R. Garske
 Surveyor's Michigan License No. 28410

Date 4-6-95

