

MAR 02 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's office }
Gogebic County } ss.

For corners in

<u>Gogebic</u> (County)	Located In:	Corner Code #
1. Public Land Survey	Section <u>27</u> ⁴⁸ T <u>48</u> R <u>48</u> <u>48</u> N <u>48</u> W <u>48</u> H <u>48</u>	
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	

Received for record the
21ST day of JULY
A. D. 1999 at 1:35 o'clock
P M., and recorded in
Liber 7 of CORNERS
on page 213
Ramona Collins Duvitt
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Quarter corner to sections 22 & 27, T48N, R47W

I, John R. Garske in a field survey on June 10, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9		*		●								
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original Survey by William Ives, D.S. in 1848.
Original bearing trees:
Hemlock 14" S29°E 19 links
B. Ash 10" N45°W 33 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I found a 1 1/2" iron pipe at the extension of the centerlines of Pump Station and Pillola Roads. The iron pipe fits well with corners east (2622.86 feet) and west (2616.08 feet).

(Research on file)

PEER GROUP APPROVED
Richard J. Deahn 7/20/99
COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I replaced the pipe with a 3/4" x 3' long aluminum rod with a 3 1/4" dia. aluminum cap stamped to identify the corner from which:

10" ash	S74°W	79.04 feet
3/4" iron rod	S15°W	82.03 feet
12" willow	N29°E	21.12 feet
steel sign rail	N55°E	3.20 feet

Signed by John R Garske
Surveyor's Michigan License No. 28410

Date 7/20/99

