

**SURVEY &
REMONUMENTATION**

JUN 29 1995

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Gogebic</u> (County)	Located In:	Corner Code #
1. Public Land Survey S-15	T <u>48N</u> R <u>47W</u>	<u>I-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____
 Section corner common to Sections 10, 11, 14 and 15, T48N, R47W.

I, John R. Garske, in a field survey on March 29, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- On September 15, 1848, William Ives set section corner post from which a 10" sugar bears S57W, 19 links and a 12" sugar - N40°E, 44 links.
- USDA Form 874-9 dated 3/26/35 - No corner evidence found. States corner location at road intersections.
- 1978 Gogebic County Road Commission plans for Lake Road show corner position.
- April 11, 1983 - 5/8" x 30" rebar at fence line intersection and road intersections extended - guy pole - S41°E, 43.76 feet; power pole - S44°W, 48.69 feet; 8" maple - N38°W, 47.16 feet. John R. Garske recorded corner in Liber 2, page 503.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found corner position as noted above and updated to county and state specifications.

P.A. 74 research on file with Register of Deeds office.

PEER GROUP APPROVED

Richard R. Dahn 4/6/95
COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I set a 3/4" diameter x 30" iron rod with a 3 1/4" diameter aluminum cap stamped: County Remonumentation; T48N, R47W; S-10; S-11; S-14; S-15; 1995; RLS 28410, from which I established the following bearing trees and/or reference objects: guy pole - S41°E, 43.76 feet; power pole - S4°W, 48.69 feet; 10" sugar - N38°W, 54.66 feet; a reference object consisting of a 2 1/2" diameter x 30" long aluminum pipe with a 3 1/4" diameter aluminum cap stamped: County Remonumentation; T48N, R47W; S-10; S-11; S-15; S-14; 1995; RLS 28410; S60°W - 43.73 feet; A 6 foot steel rail with sign 1.29 feet away.

Register's Office }
 Gogebic County }

Required for record the
12th day of APRIL
 A. D. 1995 at 1:30 o'clock
P M. and recorded in
 Liber 5 of CORNERS
 on page 244
Ramona Collins, Deputy
 Register of Deeds

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5					15	14	13						
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Signed by John R. Garske Date 4-6-95
 Surveyor's Michigan License No. 28410

