

**SURVEY & REMONUMENTATION**

JUN 29 1995

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

	<u>Gogebic</u> (County)	Located In:	Corner Code #
1. Public Land Survey	S-15	T <u>48N</u> R <u>47W</u>	<u>1-7</u>
		T _____ R _____	_____
		T _____ R _____	_____
		T _____ R _____	_____
2. Property Controlling in Section	S _____	T _____ R _____	_____
	S _____	T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____	T _____ R _____	_____
	S _____	T _____ R _____	_____

Register's Office }  
 Gogebic County }

Recorded for record this  
12<sup>th</sup> day of APRIL  
A. D. 1995 at 1:30 o'clock  
P. M., and recorded in  
 Liber 5 of CORNERS  
 on page 246.

Ramona Collins, Deputy  
 Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

Section corner common to Sections 14, 15, 22 & 23, T48N, R47W

I, John R. Garske, in a field survey on March 29, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

- On September 13, 1848, William Ives set section corner post from which a 14" Y. birch - S36°W, 30 links and a 14" Y. birch - N28°E, 44 links.
- USDA Form 874-9 dated 4/1/35 - No corner found. States corner location at road intersections. Found cedar post with tag - east, 33.0 feet.
- 1978 Gogebic County Road Commission plans for Lake Road show corner position.
- April 11, 1983 - P.K. nail - Post with U.S.F.S. tag - west, 30.5 feet; power pole - S29°E, 45.31 feet; power pole - S46°W, 55.32 feet; 8" basswood - N74°W, 53.16 feet.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

I accepted the corner position in the road centerline intersection as being true as it has been used in many surveys and is setting harmoniously with all area residents. The position was verified with measurements to corners north, south and west.

Record research on file with Register of Deeds.

**PEER GROUP APPROVED**

Richard K. Dredin 4/6/95  
**COUNTY REPRESENTATIVE**

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

I set a 3 1/4" diameter brass cap stamped: T48N, R47W; S-15; S-14; S-22; S-23; 1995; RLS 28410, from which I established the following bearing trees and reference objects: 8" R. maple - N59°E, 45.88 feet; post and U.S.F.S. tag - west, 30.5 feet; 8" ash - S28°E, 59.80 feet; power pole - S46°W, 55.32 feet; a reference monument consisting of a 2 1/2" diameter x 30" long aluminum pipe with a 3 1/4" aluminum cap stamped: County Remonumentation; T48N, R47W; R.M.; S-15; S-14; S-22; S-23; 1995; RLS 28410; S51°E, 48.74 feet; 6 foot steel rail with sign - 1.29 feet away.

Signed by John R. Garske  
 Surveyor's Michigan License No. 28410

Date 4-6-95

