

SURVEY & REMONUMENTATION

JAN 22 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

Received for record the
22ND day of DECEMBER
A. D. 1997 at 11:00 o'clock
A m., and recorded in
Liber 6 of CORNERS
on page 303
Ramona Collins, Deputy
Register of Deeds

For corners in
Gogebic

(County)

Located In:

Corner Code #

1. Public Land Survey

Section 22	48N	47W	I-8
T	R		
T	R		
T	R		
T	R		
S	T	R	
S	T	R	
S	T	R	
S	T	R	

2. Property Controlling in Section

3. Miscellaneous Property in Sec.

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

1/4 corner sections 23 & 24, T48N, R47W
22 23

I, John R. Garske, in a field survey on December 11, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

Original corner set by William Ives, D.S. in 1848.
He set a wood post from which:
Hemlock 28" N63°W 20 links
Elm 14" S65°E 44 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

The corner falls at the centerline intersection of Lake Road and Beagle Club Road. No original evidence exists. I positioned the corner at the centerline intersection. Fence lines north and south fit well with this location. The 1/4 corner south measures 2641.83 feet.

(Research on file)

PEER GROUP APPROVED
Richard L. Deahn 12/19/97
COUNTY REGISTER

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 5/8" x 10" iron rod with a 3 1/4" brass cap stamped to identify the corner 4" below the surface, from which:
Power Pole N46°E 40.90 feet
Power Pole S54°E 49.94 feet
7" S. Sugar Maple S66°E 43.17 feet
Reference Monument (R.M.) N52°W - 41.81 feet - Steel Sign Rail - 1.85 feet
(2 1/2" 30" alum. pipe with a 3 1/4" dia alum. cap)

Signed by John R. Garske
Surveyor's Michigan License No. 28410

Date 12/19/97

