

**SURVEY &
REMONUMENTATION**

OCT 03 1996

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

Register's Office }
Gogebic County } ss.

For corners in

Gogebic
(County)

Located In:

Corner Code #

- | | | | | | |
|------------------------------------|---|-----|---|-----|-----|
| 1. Public Land Survey | T | 48N | R | 47W | K-5 |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | | T | | R |
| | S | | T | | R |
| 3. Miscellaneous Property in Sec. | S | | T | | R |
| | S | | T | | R |

Received for record the
10TH day of JUNE
A. D. 1996 at 9:40 o'clock
A m., and recorded in
Liber 5 of CORNERS

on page 35B
Yamona Collins, Deputy
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Sec. cor. comm. to sec's. 11,12,13 & 14

I, John P. Goss, in a field survey on May 31, 19 96

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the cornerpoints mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by William Ives on Sept. 12, 1848. Set post.
Original bearing trees: Y. Birch 18" N 25° E 48 links
Hemlock 16" S 37° W 20 links

In 1992 Robert Mick, P.S. set a 3/8" by 24" rebar with yellow Cap No. L.S. 16936 at location of 3" by 3" cedar post along side a Keweenaw Land Assoc. Limited tag. He recoded said Section corner in Liber 4 on Page 90 of Land Corners for Gogebic County. He established the following bearing trees and reference objects. 13" Maple- S 05° W- 1.98'; 4" Maple- S 60° E- 21.82'; 5" Maple- N 67° E- 5.85'; 4" Maple- N 06° E- 29.44'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I found the 3/8" rebar with yellow cap No. L.S. 16936 set by Robert Mick. It checked with Mick witnesses. I updated the corner monument and accessories as noted below to state and county specification.

Act 74 reseach on file.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

PEER GROUP APPROVED

Richard P. Drahn 6/6/96
COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I replace the 3/8" rebar with a 2 1/2" by 30" aluminum pipe with a 3 1/4" aluminum cap stamped: County Remonumentation; S-11, S-12, S-13, S-14; 1996, P.S. 23509. I established the following bearing trees and reference objects.

- | | | |
|----------------|---------|--------|
| 14" Maple | S 05° W | 1.98' |
| 4" Elm | S 60° E | 21.82' |
| 6" Maple | N 67° E | 5.85' |
| 6" Maple | N 06° E | 29.44' |
| 6' Rail & sign | N 24° W | 2.73' |



Signed by John P. Goss

Date May 21, 1996

Surveyor's Michigan License No. 23509

Fed. No. J-21