

**SURVEY & REMONUMENTATION**

JAN 22 1998

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
Gogebic

(County)	Located in:	Corner Code #
	Section 23 48N 47W	K-8
1. Public Land Survey	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register's Office }  
Gogebic County } ss.

Received for record the  
22<sup>ND</sup> day of DECEMBER  
A. D. 1997 at 11:00 o'clock  
A. m., and recorded in  
Lib. 6 of CORNERS  
on page 306  
Ramona Collins, Deputy  
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

1/4 corner sections 23 & 24, T48N, R47W

I, John R. Garske, in a field survey on December 16, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original Township survey by William Ives, D.S. in 1847  
He set a wood post from which:  
A Hemlock 18" S35°W 12 links  
An Ironwood 9" N14°E 18 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of the original corner exists. I established the corner at the centerline intersection of Beagle Club Road extended and Skyway Lane. An ancient fence line runs west, 33 feet north of this position. Distances north and south to fence lines check relatively well. Distance north and south to monumented corners also fit with this location, 2648.71 north & 2643.15 south.

(Research on file)

**PEER GROUP APPROVED**  
Richard P. Drah 12/19/97  
**COUNTY REPRESENTATIVE**

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 5/8" x 10" iron rod with a 3 1/4" brass cap stamped to identify the corner, from which:  
6" Sugar N88°W 32.71 feet  
4" Sugar S30°E 39.36 feet  
4" Sugar S36°W 35.23 feet  
Reference Monument (R.M.) S50°E 25.55 feet  
(2 1/2" x 30" alum. pipe with a 3 1/4" alum. cap)  
Steel Sign Rail S50°E 1.32 feet from R.M.

Signed by John R. Garske  
Surveyor's Michigan License No. 28410

Date 12/19/97

