

SURVEY & REMONUMENTATION

JAN 22 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

Received for record the
22nd day of December
A. D. 1997 at 11:10 o'clock
A m., and recorded in
Liber 6 of CORNERS
on page 308
Ramon Collins, Deputy
Register of Deeds

For corners in
Gogebic

(County)	Located In:	Corner Code #
	Section 26 48N 47W	K-10
1. Public Land Survey	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

1/4 corner section 25 & 26, T48N, R47W

I, John R. Garske, in a field survey on December 11, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original Township survey by William Ives, D.S. in 1848.
He set a wood post from which:
Hemlock 6" S28°E 18 links
Y. Birch 10" N20°W 28 links

PEER GROUP APPROVED
Richard L. Deahn 12/18/97
DOUGLAS BAZZUCCHI

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I found no evidence of the original corner position due to road and airport runway construction. The corner would have been at the intersection of Skyway Road and North Airport Road which was eliminated due to new runway construction. No remains of the road bed exists. I set the corner at the centerline extension of Skyway Road at a doubled over distance from a fence line at the south 1/16th corner This location checks well with fence lines north for the next mile. (see sketch on back)

(Research on file)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:



The corner falls 182 feet north of the main runway at the Gogebic-Iron County Airport. At the 1/4 corner I set a 3/4" 30" iron rod with a 3 1/4" dia. alum. cap, stamped to identify the corner from which I set two witness corners on the section line north, consisting of 3/4" dia. x 30' iron rods with 3 1/4" dia. alum. caps.

W.C. North 300.00 feet S.S.P. 1.70' north
W.C. North 500.00 feet S.S.P. 1.00 north

Both corners are stamped and set flush with the ground. The 1/4 corner is an open area and no other bearing objects exist.

Signed by John R Garske
Surveyor's Michigan License No. 28410

Date 12/19/97

SURVEY &
REMONUMENTATION

JAN 22 1998

SECTION

SKETCH


No Scale

at Location
OF OLD
ROAD
INTERSECTION
(Destroyed)

