

SURVEY & REMONUMENTATION

JAN 22 1998

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

Received for record the
22ND day of DECEMBER
A. D. 1997 at 11:10 o'clock
A m., and recorded in
Liber 6 of COGNAC
on page 309
Ramona Collins, Deputy
Register of Deeds

For corners in SECTION
Gogebic

(County)	Located In:	Corner Code #
1. Public Land Survey	Section 25 <u>48N 47W</u> <u>M-9</u>	<u>A-9</u>
	<u>T48N R 46W</u>	
	T R	
	T R	
	T R	
2. Property Controlling In Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Section corner 24, 25, 19 & 30, T48N, R47-46W

I, John R. Garske, in a field survey on December 11, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		16		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original Township survey by William A. Burt in 1847.
Set Tamarack post from which:
Tamarack 9" N44°W 15 links
Tamarack 7" N29°E 28 links
Stream 10 links wide - south 1 chain.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I found no evidence of the original survey. The corner location now falls in the centerline of Bale Lane. I found an ancient fence line running west, consisting of barb wire & posts. I set the corner on the fence line extended in the centerline of Bale Lane. The creek crossing Bale Lane south of the corner has been dug and channeled and only measures 43 feet south. This corner position checks well with fence lines south along Bale Lane to the 1/4 corner and section corner at Airport Road.

(Research on file)

PEER GROUP APPROVED
Richard L. D. [Signature] 12/19/97
COURT REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I set a railroad spike at the corner position from which I set two reference monuments consisting of 3/4" dia. x 3' alum. rod with 3 1/4" dia. alum. caps stamped:
R.M.1 - Due West 31.23 feet
Steel Sign Rail 1.48 feet, 32.71 feet to corner
R.M.2 - Due East 31.32 feet
Steel sign Rail 1.73 feet, 33.05 feet to corner
Monuments are set on line with corner
Power Pole S18°E 92.06 feet
S00°-01'-16" E - 2624.70 - to 1/4 cor. 25&30

Signed by John R. Garske
Surveyor's Michigan License No. 28410

Date 12/19/97

