

MAY 16 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Gogebic  
(County)

Located In: Corner Code #

1. Public Land Survey

T48NR 48W B-1  
T49NR 48W B-13

2. Property Controlling in Section

S \_\_\_ T \_\_\_ R \_\_\_

3. Miscellaneous Property in Sec.

S \_\_\_ T \_\_\_ R \_\_\_  
S \_\_\_ T \_\_\_ R \_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

1/4 cor. comm. to sec's 6 & 31

I, John P. Goss, in a field survey on Sept. 17, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by William A. Burt on Sept. 13, 1847. Set Cedar post  
Original bearing trees: 6" Maple - N 09° E- 32 links  
6" W. Birch- N 65° W- 10 links.

John Garske found sq. maple post, a 10" balsam bearing tree blazed with tag from Gogebic County Forest Dept. Corner was reestablished using above and GLO calls for a stream 8 links wide 148.5 feet east and found decay Maple stump at recorded distance and bearing for original bearing tree. John Garske place a 2 1/2" iron pipe with stamped brass cap: T49N, R48W; 1/4, S-6, S-31, 1988, RLS 28410, with the following bearing trees

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

4" W. Birch N 27° W 17.43' John Garske recorded said corner in  
10" Balsam Due East 25.82' Liber 3, page 274 of Land Coners for  
8" Red Maple S 05° E 37.64' Gogebic County.

I found the 2 1/2" iron pipe with brass cap and it checked with Garske witnesses. I updated the accessories as noted below to state and county specification.

Act 74 research on file.

PEER GROUP APPROVED  
Richard P. Drach 12/11/96  
COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

From the 2 1/2" iron pipe with brass cap. I established the existing and new bearing trees and reference objects.

5" W. Birch N 27° W 17.43'  
10" Balsam Due East 25.82'  
9" Red Maple S 05° E 37.64'  
8" Red Maple S 21° W 48.28'  
6' Rail & sign S 33° W 1.21'

Measurements are to nail in side of tree.

Signed by John P. Goss  
Surveyor's Michigan License No. 23509  
Fed No. Z-3

Date Sept. 18, 1996

Register's Office }  
Gogebic County } ss.

Received for record the  
12<sup>TH</sup> day of December  
A. D. 1996 at 2:30 o'clock  
1<sup>P</sup> m., and recorded in  
Liber 6 of CORNERS  
on page 89.  
Ramona L. Collins, Deputy  
Register of Deeds

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1		●											
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13		●											