

**SURVEY & REMONUMENTATION**

AUG 08 1997

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }  
Gogebic County } ss.

Received for record the  
11<sup>th</sup> day of JUNE

A. D. 1997 at 10:35 o'clock  
A m., and recorded in

Liber 6 of CORNERS  
on page 138

*Colleen M. Kibak, Deputy*  
Register of Deeds

Register of Deeds Stamp & File Number

For corners in

GOGEBIC

(County)

Located In:

Corner Code #

1. Public Land Survey

T49N R48W F-13  
T48N R48W F-1

2. Property Controlling in Section

S T R  
S T R

3. Miscellaneous Property in Sec.

S T R  
S T R

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

Quarter Corner common to Sections 33 & 4, T49N & T48N, R48W.

I, Earl W. Applekamp, in a field survey on May 21, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1					●							
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13					●							

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by William A. Burt, U.S. Deputy Surveyor, September 13, 1847. Set Wood Post.

ORIGINAL BEARING TREES:

12" HEMLOCK N27°E 25.08 feet  
12" Cedar N63°W 24.42 feet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence was found due to construction of Lake Road. No current evidence of the corner was found. Corner was re-established by single proportionate measure and on line with opposite Section corners to the East & West.

Research on file with the Gogebic Remonumentation Representative.

PEER GROUP APPROVED  
*Richard L. Deahn 6/10/97*  
COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 2½"X30" aluminum pipe with a 3" stamped cap 19.9 feet South of the centerline of Lake Road and flush with the ground 5 feet North of the ditch. I established a reference monument, a 2½"X30" aluminum pipe with a 3" cap stamped to read: County Remonumentation, T49N, T48N, R48W, ¼, S33, S4, 1997, P.S. 17610. I established three bearing trees.

7" Maple N43°W 73.31 feet - 7" Basswood S46°E 58.17 feet  
4" Maple N19°E 73.89 feet - REF. MON. S19°W 36.33 feet



Signed by Earl W. Applekamp  
Surveyor's Michigan License No. 17610

Date May 29, 1997