

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in Gogebic Located in: Corner Code #  
 (County)

1. Public Land Survey T48NR48W I-3  
 T R  
 T R  
 T R
2. Property Controlling S T R  
 in Section S T R
3. Miscellaneous S T R  
 Property in Sec. S T R
4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_
- Section Corner common to Sections 2, 3, 10 and 11.

**SURVEY &  
 MONUMENTATION**

**JAN 05 2001**

**SECTION**

Register's Office }  
 Gogebic County } ss.

Received for record the  
2<sup>ND</sup> day of JUNE  
 A. D. 19 00 at 10:30 o'clock  
A m., and recorded in  
 Liber 7 of CORNERS  
 page 373  
*Cheryl Rupp, Esq.*  
 Register of Deeds

Register of Deeds Stamp & File  
 Number

I, John R. Garske, in a field survey on May 1, 2000, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and / or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**A. Description of original monument and accessories and / or subsequent restoration:**

Original survey by William Ives in 1848.  
 Original Corner: Wood post  
 Original Bearing Trees: 16" Sugar Maple N 56° E 18 Links  
 16" Sugar Maple S 68° W 21 Links

**B. Description of corner evidence found and / or method applied in restoring or re-establishing corner:**

I found a 1 1/2" iron pipe with a 1/2" iron pipe beside it. A blueline runs East-West with a ribbon line North-South from the pipe. I also found a bearing tree tag placed by Keweenaw in 1980. I replaced the 1 1/2" iron pipe with a new aluminum monument upon examining the found evidence and traverse measurements to other known corners.

Record research on file.  
 (See sketch on back)

*Richard L. Dredman* 5/24/00  
 COUNTY SURVEYOR

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

I set a 30" x 3" split-bottom Bernsten monument at the above described section corner position, from which I established the following witnesses:

7" Sugar Maple	N 10° W	13.93 Feet
8" Sugar Maple	S 52° E	6.14 Feet
6" Sugar Maple	S 65° W	12.06 Feet
Steel Sign Post	S 09° E	1.0 Feet

Signed by John R. Garske

Date 5/24/00

Surveyor's Michigan License No. 28410  
 FB # 248, page 75




Quarter Corner common to Sections 2 & 11,  
T 48 N, R 48 W.

SURVEY &  
REMONUMENTATION

JAN 05 2001

SECTION



Not to scale

(~~±~~T" Intersection)

⊕ / ⊕ checks with split

