

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Gogebic Located in: _____ Corner Code # _____
 (County)

1. Public Land Survey T48NR48W J-3
 T _____ R _____
 T _____ R _____
 T _____ R _____
 T _____ R _____
2. Property Controlling S _____
 In Section S _____
 3. Miscellaneous S _____
 Property in Sec. S _____
4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____
- SECTION**
- Quarter Corner common to Sections 2 and 11.

Register's office }
 Saginaw County } SA.

Received for record the
2ND day of JUNE
 A. D. 19 00 at 10:30 o'clock
A m., and recorded in
 Liber 7 of CORNERS
 page 374
Cheryl Reppe Dep.
 Register of Deeds

Register of Deeds Stamp & File
 Number

I, John R. Garske, in a field survey on May 1, 2000, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and / or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3										●			
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and / or subsequent restoration:

Original survey by William Ives in 1848.
 Original Corner: Wood post
 Original Bearing Trees: 7" Sugar Maple N 44° E 5 Links
 8" Balsam S 78° W 11 Links

B. Description of corner evidence found and / or method applied in restoring or re-establishing corner:

No evidence of original corner was found.
 I set the corner at the centerline-centerline intersection of two roads.

Record research on file.

DEED GROUP APPROVED
Richard P. Deahn 5/24/00
 COUNTY DEEDS DIVISION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I set a 3/4" aluminum cap on a 5/8" x 30" rebar, from which I established the following witnesses:

5" Maple	N 41° E	58.41 Feet
5" Maple	S 61° W	21.22 Feet
8" Maple	N 54° W	57.42 Feet
Reference Monument	S 29° W	18.66 Feet

Signed by *John R. Garske*



Surveyor's Michigan License No. 28410
 FB # 248, page 86-87

Quarter Corner common to Sections 2 & 11,
T 48 N, R 48 W.



SURVEY &
REMONUMENTATION

JAN 05 2001

SECTION

Not to scale

($\frac{E}{E}$) Intersection

$\frac{E}{E}$ / $\frac{E}{E}$ checks with split

