

SURVEY & REMONUMENTATION

OCT 03 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
 Gogebic County } ss.

Received for record the
16TH day of CORNERS
 A. D. 19 96 at 10:30 o'clock
A m., and recorded in
 Liber F of CORNERS
 on page 404
Ramona Collins, Deputy
 Register of Deeds

Register of Deeds Stamp & File Number

For corners in

Gogebic
 (County)

Located In:

Corner Code #

- | | | |
|------------------------------------|---------------------------|------------|
| 1. Public Land Survey | T <u>48N</u> R <u>47W</u> | <u>A-5</u> |
| | <u>48N</u> R <u>48W</u> | <u>M-5</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____
 Section corner 12, 13, 7 & 18; T.48 N., R.47-48 W.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2				
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, John P. Goss, in a field survey on July 23, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
 Original corner established by William Burt, in 1847.
 Original bearing trees
 1. Spruce 9" N 18° E 40 links (26.40')
 2. Hemlock 16" S 47° W 23 links (15.18')
 3. Hemlock 14" S 68° E 55 links (36.30')
 4. Spruce 8" N 62° E 31 links (20.46')

Richard L. Drahn & John P. Goss, both R.L.S. restored the corner position at record bearing and distance from the remains of the original bearing trees. At the corner position they set a 1 1/2" I.D. by 4 foot long, concrete filled, iron pipe, capped with a 3" circular brass table which reads: T.48 N., R.47-48 N.; S-12, S-13, S-7, S-18; 1978; R.L.S. 23509. From which

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: they established the following new blazed and scribed bearing trees:
 10" Hemlock N. 12° W. 20.6' And
 12" Hemlock S. 88° E. 28.0' recorded said corner in Liber 1 on pages
 3" Red Maple S. 42° W 26.6' 402 and 403 of Land Corners for Gogebic County.

I found the 1 1/2" I.D., iron pipe with 3" Circular brass table and it checked with Drahn and Goss witnesses. I updated the accessories as noted below to state and county specification. All of the evidence found in 1978 survey still at this location.
 Act 74 research on file.

PEER GROUP APPROVED
Richard L. Drahn 8/9/96
 COUNTY REPRESENTATIVE

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 From the 1 1/2" iron pipe with 3" brass table, I established the following existing and new bearing trees and reference objects.

- | | | |
|----------------|---------|--------|
| 14" Hemlock | N 12° W | 20.60' |
| 16" Hemlock | S 88° E | 28.01' |
| 4" Red Maple | S 42° W | 27.64' |
| 6" Hemlock | N 56° E | 7.88' |
| 6" rail & sign | N 03° W | 1.12' |



Signed by John P. Goss Date July 24, 1996

Surveyor's Michigan License No. 23509
 Fed No. J-1 & J-25