

SURVEY &
REMONUMENTATION

FEB 18 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Gogebic
(County)

Located in:

Corner Code 4

1. Public Land Survey Section 11T 48N R 49W
 T _____ R _____
 T _____ R _____
 T _____ R _____
2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

One-quarter corner Section 11 & 12.

I, John R. Garske, in a field survey on December 6, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original survey by William Ives, Deputy Surveyor, on August 11, 1848. Set quarter section post (north to south). Bearing trees:

- 5" cedar - N61°W - 16 links
- 6" Y. birch - S32°E - 23 links

No original evidence found.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Established the one-quarter corner by single proportional measurement between opposing section corners on line and one-half the distance in accordance with the original government survey notes.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set standard Bernsten 2 1/2" aluminum pipe with 3 1/2" aluminum cap stamped: County Remonumentation; T48N, R49W; 1/4 cor.; S-11; S-12; 1993; RLS 28410. Established the following bearing trees and reference objects:

- Power pole L.S.D.P. #11-93/51 - N81°W - 61.78 feet
 - 7" H. maple - N89°E - 39.66 feet
 - Steel sign post - S-47°E - 1.44 feet
 - 10" WHITE BIRCH - S.06°W. - 15.81 FEET
 - C.L. OF POWERS ROAD - WEST 29 FEET
- R.L.D. 12/30/93

Signed by John R. Garske
 Surveyor's Michigan License No. 28410

Date 12/20/93

Register's Office }
 Gogebic County } ss.

Received for record the
30th day of DECEMBER
 A. D. 1993 at 12:30 o'clock
P m., and recorded in
 Liber 4 of CORNERS
 on page 340.
Betty Isaac Deputy
 Register of Deeds

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

