

DEC 15 1998

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office  
Gogebic County

Received for record the  
25<sup>th</sup> day of NOVEMBER  
A. D. 1998 at 10:00 o'clock  
A m., and recorded in  
Liber 7 of CORNERS  
on page 95.  
Ramona Collins, Deputy  
Register of Deeds

SECTION  
For corners in  
**Gogebic**

	Located In:		Corner Code #		
	Section	1	48N	49W	L-3
1. Public Land Survey	T	R			
	T	R			
	T	R			
	T	R			
2. Property Controlling in Section	S	T	R		
	S	T	R		
3. Miscellaneous Property in Sec.	S	T	R		
	S	T	R		

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

1/4 corner sections 1 & 12, T48N, R49W

I, John R. Garske, in a field survey on September 9, 1998 hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4			3			2
3													1
4	7			8			9			10			11
5													12
6	18			17			16			15			14
7													13
8	19			20			21			22			23
9													24
10	30			29			28			27			26
11													25
12	31			32			33			34			35
13													36

A. Description of original monument and accessories and/or subsequent restoration:

Original Township survey by William Ives, D.S. Aug. 9-16, 1848

Bearing Trees:

8" Fir N40°E 23 links (15.18')  
8" Sugar S62°W 22 links (14.52')

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I established a corner position from which to search by single proportional methods. No evidence could be found of the original corner position. I found an iron pipe 31 feet west of our corner which a local resident said was set by his father. I monumented the corner at the single proportional position.

(Research on file)

PEER GROUP APPROVED  
Richard L. Wahn 11/24/98  
COUNTY REGISTER

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I set a 3/4" x 48" aluminum rod monument with a 3 1/4" aluminum cap, stamped to identify the corner from which I established:

6" maple N76°E 18.53 feet  
8" maple S25°E 5.92 feet  
3/4" iron pipe S88°W 31 feet  
8" maple N5°W 20.08 feet  
6' steel sign rail Due North 1.71 feet

Signed by John R. Garske  
Surveyor's Michigan License No. 28410

Date 11/24/98

