

DEC 1 1998

Section

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

Received for record the
25TH day of NOVEMBER
A. D. 1998 at 10:00 o'clock
A m., and recorded in
Liber 7 of CORNERS
on page 94
Romona Collins Deputy
Register of Deeds

For corners in
Gogebic
(County)

Located In:	Corner Code #
Section 1	<u>48N 49W M-3</u>
T <u>48N 48W</u>	<u>A-3</u>
T	R
T	R
T	R
T	R
S	T R
S	T R
S	T R
S	T R

- Public Land Survey
- Property Controlling in Section
- Miscellaneous Property in Sec.

Register of Deeds Stamp & File Number

- Lot No. _____, Recorded Plat _____
- Private Claims _____

Section Corner to 1, 12, 6 and 7, T48N, R48-49W

I, John R. Garske in a field survey on 9-9, 1998 hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original Township survey by William A. Burt, D.S. in Sept. 1847
 He established Bearing Trees:
 Y. Birch 12" S34°E 21 links (13.86 feet)
 Lynn 14 " N33°E 29 links (19.14)
 Original Township subdivision by William Ives, D.S. in Aug. 1848.
 He established: :
 Hemlock - 18" S55°W 31 links (20.46 feet)
 DO 20" N23°E 42 links (27.72 feet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

PEER GROUP APPOINTED
Richard L. Walsh 11/24/98
COUNTY ISHTABENA

At the corner position I found an old post with a 1964 Keweenaw Tree Tag on a 8" maple set by H.D. bearing N18°E, 6.32 feet. I could find no remains of the original bearing trees. This corner position works well with the natural feature calls of a Ravine 1650' west and a stream 1174.8 feet east. The 1/4 corner to 1 and 6 bears N00°-17'-27" E - 2639.08 feet and the 1/4 corner to 1 and 12 bears S89°-39'-44" W - 2615.22 feet.

(Research on file)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I set a 3/4" x 48" aluminum rod with a 3 1/4" dia. aluminum cap stamped to identify the corner, from which I established:

8" maple	N18°E	6.32 feet
7" maple	84°W	10.67 feet
7" maple	S07°W	10.67 feet
Steel sign rail	S54°E	1.62 feet

Signed by John R. Garske
Surveyor's Michigan License No. 28410

Date 11/24/98

