## MAR 02 2000

For corners in

## LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

			60	
	•		 <i>6- 0</i>	
			rde	
			R/	
				Dion

SECTION Gogebic Located In: Corner Code # (County) 1. Public Land Survey T 48N R 45W. A-1 T<u>48N</u> R<u>46W</u> M-1 T 49N R 45W A-13 T 49N R 46W M-13 2. Property Controlling in Section 3. Miscellaneous

Property in Sec. Register of Deeds Stamp & File Number

3

5

6

ន


10

4. Lot No. , Recorded Plat 5. Private Claims

Section Corner 6, 1, 31 & 36; T.48-49 N., R.45-46 W.

Richard L. Drahn , in a field survey on August 22, , 19 99 that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.



Original corner established by Austin Burt on 9/9/1847. Original bearing trees:

Maple

14

S.65° E.

24 links

(15.84')(23.10)

N.69° W. Maple 14" 35 links

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I restored the corner position at record bearing and distance from the stump holes of the two original bearing trees.

Distance checks to recovered quarter corners 36.05 chains east and 39.88 chains south.

A 3/4" X 2' iron pipe set by compass and chain by the Gogebic County Forestry Commission bears S.89° E., 10.8 feet.

Corner research on file with Gogebic County records.

## C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 2" x 30" aluminum pipe monument with a 3 1/4" stamped aluminum cap and the Following new B.T.s (all measurements taken to a nail in side of tree):

Sugar Maple 6" N.67° E. 23.951 Red Maple 10° N.05° W. 28.00 S.48 °W. **Red Maple** 12" 19.70 Steel sign rail N.83° W. 2.01

BICH, RICHARD L. DRAHN LAND SURVEYOR No. 21564

Date \_\_\_August 23, 1999

Surveyor's Michigan License No.\_

21564

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, REVISED MAY 14,1975

REVISED JAN., 1983 REVISED OCT., 1996