

**SURVEY &  
MONUMENTATION**

JAN 05 2001

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }  
Gogebic County } ss.

Received for record the  
25<sup>TH</sup> day of August  
A. D. 2000 at 1:20 o'clock  
P. m., and recorded in  
the LIBER B of CORNERS  
page 20  
Phonema Collins Deputy  
Register of Deeds

For corners in SECTION

<u>Gogebic</u> (County)	Located In:	Corner Code #
1. Public Land Survey	<u>T48N R 45W</u>	<u>D-1</u>
	<u>T</u> <u>R</u>	
	<u>T</u> <u>R</u>	
	<u>T49N R 45W</u>	<u>D-13</u>
2. Property Controlling in Section	<u>S</u> <u>T</u> <u>R</u>	
	<u>S</u> <u>T</u> <u>R</u>	
3. Miscellaneous Property in Sec.	<u>S</u> <u>T</u> <u>R</u>	
	<u>S</u> <u>T</u> <u>R</u>	

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

$\frac{1}{4}$  Corner 5 & 32; T.48-49 N., R.45 W.

I, Richard L. Drahn in a field survey on Aug. 16, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1			●									
2	6		5	4	3				2		1	
3												
4	7		8	9	10				11		12	
5												
6	18		17	16	15				14		13	
7												
8	19		20	21	22				23		24	
9												
10	30		29	28	27				26		25	
11												
12	31		32	33	34				35		36	
13			●									

A. Description of original monument and accessories and/or subsequent restoration:  
Original corner established by Austin Burt on 9/9/1847. Original B.T.s:

Y. Birch	10"	N.35 E.	13 links	( 8.58')
Y. Birch	10"	N.55 W.	17 links	(11.22')

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
I restored the corner position at record bearing and distance from the remains of the two original bearing trees. The first is a series of root holes with Yellow Birch Bark and identifiable wood. The second one is now a series of root holes half buried by logging road construction debris with fragments of Yellow Birch bark. The 40.00 chain distance east and west to recovered corners is in accord with the field notes of the original Government survey.  
A 9" Red Maple blazed and painted for the corner bears S.12 W. 10.8 feet.

Corner research on file with Gogebic County records.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

At the corner position I set a 3/4" X 4" solid aluminum marsh rod with a stamped aluminum cap and the following new bearing trees:

Yellow Birch	6"	N.24 E.	21.27'
Black Ash	8"	S.62 E.	36.35'
Sugar Maple	12"	N.74 W.	18.36'
Steel sign rail	6'	N.75 E.	1.56'

DEED GROUP APPROVED  
Richard L. Drahn 8/23/00  
COUNTY REGISTER OF DEEDS



Signed by Richard L. Drahn Date August 17, 2000  
Surveyor's Michigan License No. 21564