

MAR 02 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

For corners in

Received for record the
22nd day of SEPTEMBER
A. D. 1999 at 1:00 o'clock
P m., and recorded in
Lib. 7 of CORNERS
on page 246
Ramona Collins Deputy
Register of Deeds

<u>Gogebic</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>48</u> N R <u>45</u> W.	<u>G-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T <u>49</u> N R <u>45</u> W.	<u>G-13</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Section Corner 3, 4, 33 & 34; T.48-49 N., R.45 W.

I, Richard L. Drahn, in a field survey on September 7, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Austin Burt on 9/9/1847. Original bearing trees:

Cedar	12"	N.63° E.	6 links	(3.96')
Fir	10"	N.67° W.	22 links	(14.52')

Louis Serena on 4/19/35 recovered a 24" long Cedar stake at this location. He placed a location poster on the south side of a 12" Cedar. The post lay south, 20 feet from the tag tree.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Restored corner position at record bearing and distance from the original Cedar bearing tree. It is now portions of badly decayed Cedar wood and roots. No evidence remains of the original Fir bearing tree.

Recovered Louis Serena's location poster on a 17" Cedar stub bearing N.13° E. 19.8' No evidence remains of the 1935 Cedar stake.

A 1" X 4" iron pipe bears S.60° W., 28.5' from the original corner location. A downed Cedar post lays S.39° W., 23.5' from the original corner location

Corner research on file with Gogebic County records.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 3/4" X 4' aluminum rod monument with a 3 1/4" stamped aluminum cap and the following new B.T.s (all measurements taken to a nail in side of tree)

Red Maple	7"	N.84° W.	13.37'
Yellow Birch	8"	N.21° E.	32.29'
Red Maple	6"	S.66° E.	8.34'
Steel sign rail	6'	S.14° W.	2.38'

DEER GROUP APPROVED

Richard L. Drahn 9/21/99
COUNTY REGISTRAR



Signed by Richard L. Drahn Date September, 1999

Surveyor's Michigan License No. 21564

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1976
REVISED JAN., 1983
REVISED OCT., 1986