

MAR 02 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office
Gogebic County

Received for record the
26th day of AUGUST
A. D. 1999 at 1:40 o'clock
P m., and recorded in
Liber 7 of CORNERS
on page 233
Ramona Collins Deputy
Register of Deeds

For corners in

<u>Gogebic</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>48N</u> R <u>45W</u>	<u>K-1</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u>49N</u> R <u>45W</u>	<u>K-13</u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Section Corner 1, 2, 35 & 36; T.48-49 N., R.45 W.

I, Richard L. Drahn, in a field survey on July 25, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
Original corner established by Austin Burt on 9/9/1847. Original bearing trees:

Hemlock	18"	N.69° E.	25 links	(16.50')
Hemlock	12"	N.26° W.	27 links	(17.82')

Corner restored by Neal Sperhake, RLS 7876, on 11/9/61 from the remains of the N.69 E. B.T. He set a 1" X 36" iron pipe monument with a 4" diameter stamped aluminum cap and the following new B.T.s:

Cedar	4"	S.21° E.	31 links	(20.46')
Maple	12"	S.67° W.	28 links	(18.48')
Cedar	7"	N.35° W.	31 links	(20.46')
Yellow Birch	5"	N.40° E.	30 links	(19.80')

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner position found marked by the monument as described, at record bearing and distance from the decayed Hemlock stump remains of the two original bearing trees and from Sperhakes bearing trees as follows:

Cedar	9"	S.20° E.	20.81'	new nail
Red Maple stub	13"	S.67° W.	18.98'	new nail
Cedar	8"	N.35° W.	20.32'	new nail
Yellow Birch	6"	N.40° E.	19.95'	new nail

Corner research on file with Gogebic County records.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

New bearing objects referenced:

Yellow Birch	6"	N.63° E.	13.42'
Steel sign rail	6"	S.58° W.	1.86'

DEED GROUP APPROVED

Richard L. Drahn 8/24/99
COUNTY REGISTER



Signed by Richard L. Drahn Date August 10, 1999

Surveyor's Michigan License No. 21564

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983
REVISED OCT., 1995