Register's Office

EAND CORNER RECORDATION CERTIFICATI								E bogeoic county										
For corners in			Filing Requirement of Act 74, Mich. P.A. 1970							Re	ceive	d for	r rec	ord	the			
roi comers in			1															
,	Gogebic (County)		Locate	d In:	Corner Code =##			A. D. 19.25 at 10:05 o'clock										
									Am., and recorded in									
1.	Public Land Survey	S-10	· ·	R\ <u>49N</u> R	R46W I		· · · · · · · · · · · · · · · · · · ·		Liber 5 of COLNERS									
				R				1	Pa	ge3	17.		•	^				
_		_	<u> </u>	R				X	an	ono	<u>.</u> C	W	W.	14	ut	IJ-		
	Property Controlling		T R										er o					
	in Section					1						,						
3.	Miscellaneous			R			Regi	ster	of D	eeds	Star	nip &	File	Nun	nber	r		
	Property in Sec.	s	T	R														
4.	Lot No	, Recorded	Plat					А	В	C D	E	F G	н	1 J	ĸ	L M		
5.	Private Claims							ıГ	Ť	ŤŤ	Ť	ÌΤ	Ť	ΪŤ	Ť	Ť		
	One quarter corner co	ommon to S	Sections 3	3 & 10, T49	N, R46W			2	- 6	5-	╁	╏╼╌┼╌	- <u>3</u>	ż	+	-i-		
			:					3	╁	$\vdash \vdash$				╂╌┼	-			
	* .				g).E	4 ├		8-	+-:		i <mark>o</mark>	┼╌┆	+			
l, _		$_$, in a fie	ld survey	on	September 13	, 19	 !	5 -	-		+-			╁┷┼				
	hereby certify that under i							6	-1 <mark>8</mark>	-17-	1	6	-15	14	-	13		
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land								7	1		1	\vdash		1-1				
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and					and 5	8_	-19	20-		1	_ _22	2:	,	_24				
				of the Michigan Board of Land Surveyors or by a Decree of a led, monumented, re-monumented, recovered, found as				9	1	\perp								
Court of Law; established, re-estable expressed below:			shed, moi	numented, r	e-monumented	i, recovered, four	nd as	10	30		1.		_} _37					
,	· ·					1	11	-30— 	Γí	1-]			ا			
NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.						•	12	\top	П	T	\sqcap	\top						
	on this certificat	· G.						13	-31— 1	32-	╀³	3-	-34 	35	十	36-		
A.	Description of origina	al monumei	nt and ac	cessories	and/or subsec	quent restoration	n:	13 [
	Original township su	rvey by Jol	hn and W	/illiam Burt	, D.S., Septem	ber 1847.												
	Original township su Fir 5" - N10°E, Cedar 8" - S5°E	5 links	y Willian	m Burt, D.S	., 1848. Origi	nal bearing trees	: Set cedar	post	;									

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I found a 3 7/8" I.D. iron pipe with a brass cap with a punch mark in the center with no stamping. The monument is similar to monuments found on the west side of the section set by the Gogebic County Park Commission, date unknown. A single proportional position falls S28°-05'-15"E, 41.63 feet from this monument. No evidence was found at the proportioned point. A standing dead 14" cedar blazed bears \$10°E, 9.90 feet from the monument matching the original B.T. reasonably well. Also blazed, ribboned lines run north, east and west. The distance of 10.9 chains west (719.4') to the east bank of the Black River checks very well to the monument. I am accepting the monument as being the best position for the one-quarter corner.

(Record research on file).

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Accepted the 3 7/8" I.D. iron pipe with brass cap and established the following bearing trees/objects:

5" S. maple - S68°E, 18.95 feet 7" ash - S62°W, 46.41 feet 7" S. maple - N10°E, 48.15 feet Steel Sign Post - S70°W, 1.22 feet

JOHN R GARSKE LAND SURVEYOR No. 28410

Signed by

Surveyor's Michigan License No.

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1911 REVISED MAY 14, 1975 REVISED JAN., 1983