

**SURVEY & REMONUMENTATION**

OCT 03 1996

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

Register's Office }  
 Gogebic County } ss.

Received for record the  
16<sup>TH</sup> day of AUGUST  
 A. D. 1996 at 10:30 o'clock  
A m., and recorded in  
 Liber 5 of LAND CORNERS  
 on page 406  
Ramona Collins Deputy  
 Register of Deeds

Register of Deeds Stamp & File Number

For corners in Gogebic (County) Located In: Corner Code #

1. Public Land Survey	T <u>49N</u> R <u>47W</u>	<u>F-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

1/4 cor. comm. to 16 & 21

I, John P. Goss, in a field survey on August 3, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by William Ives on Sept. 30, 1848. Set post. Original bearing trees: 12" Hemlock N 61° E 10 links  
 12" Hemlock S 46° W 15 links.

John Garske, found a 3/4 inch iron pipe at location of corner. He set a 2" iron pipe with 2" brass cap marked to indicated the corner position. He recorded said corner location in Liber 2 on page 511 of Land Corners for Gogebic County. He established the following bearing trees and reference objects. 6" Y. Birch- S 52° E- 16.11; 6' Maple N 44° E- 25.22'; 8" Maple S 78° W- 19.28'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I found the 2" iron pipe with 2" brass cap and it checked with Garske witnesses. I updated the accessories as noted below to state and county specification.

Act 74 research on file.

PEER GROUP APPROVED  
Richard P. Dehn 8/8/96  
 COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

From the 2" iron pipe with brass cap. I established the existing and new bearing trees and reference objects.

8" Y. Birch	S 78° W	19.28'
7" Maple	S 44° E	25.22'
8" Maple	N 52° E	16.11'
8" Maple	N 23° W	16.15'
6' Rail & Sign	N 08° W	1.19'



Signed by John P. Goss Date Aug. 5, 1996  
 Surveyor's Michigan License No. 23509