

**SURVEY & REMONUMENTATION**

OCT 03 1996

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

Register's Office }  
 Gogebic County } ST.

For corners in

Gogebic  
 (County)

Located in:

Corner Code #

- 1. Public Land Survey T 49N R 47W G-7
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

Registered for record the  
16<sup>TH</sup> day of AUGUST  
 A. D. 1996 at 10:30 o'clock  
A M., and recorded in  
 Liber 5 of CORNERS  
 on page 408  
Kamona Collins, Deputy  
 Register of Deeds

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
  - 5. Private Claims \_\_\_\_\_
- Sec. cor. comm. to sec's. 15,16,21 & 22

| A  | B  | C  | D  | E  | F  | G  | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| 2  | 6  | 5  | 4  | 3  | 2  |    |   |   |   |   |   |   |
| 3  |    |    |    |    |    |    |   |   |   |   |   |   |
| 4  | 7  | 8  | 9  | 10 | 11 | 12 |   |   |   |   |   |   |
| 5  |    |    |    |    |    |    |   |   |   |   |   |   |
| 6  | 18 | 17 | 16 | 15 | 14 | 13 |   |   |   |   |   |   |
| 7  |    |    |    |    |    |    |   |   |   |   |   |   |
| 8  | 19 | 20 | 21 | 22 | 23 | 24 |   |   |   |   |   |   |
| 9  |    |    |    |    |    |    |   |   |   |   |   |   |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 |   |   |   |   |   |   |
| 11 |    |    |    |    |    |    |   |   |   |   |   |   |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 |   |   |   |   |   |   |
| 13 |    |    |    |    |    |    |   |   |   |   |   |   |

I, John P. Goss, in a field survey on August 3, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by William Ives on Sept. 28, 1848. Set post.  
 Original bearing trees: 14" Hemlock S 29° W 13 links  
 12" Sugar Maple N 25° E 35 links

John Garske found a 3/4 inch iron pipe and 1 GLO bearing tree stump at the location; He set a 2" iron pipe with 2" brass cap marked to indicated the corner position. He recorded said corner location in Liber 2 on page 509 of Land Corners for Gogebic County. He established the following bearing trees and reference objects. 6" Y. Birch- S 22° E- 12.14'; 6" Maple- N 22° E- 15.55'; 8" Maple- N 77° W - 79.15'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I found the 2" iron pipe with brass cap and it checked with Garske witnesses. I updated the accessories as noted below to state and county specification.

Act 74 research on file,

PEER GROUP APPROVED  
Richard P. Deahn 8/8/96  
 COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

From the 2" iron pipe with brass cap. I established the existing and new bearing trees and reference objects.

- 6" Y. Birch (dead) S 22° E 12.14'
- 7" Maple N 22° E 15.55'
- 5" Maple N 77° E 7.80'
- 6' Maple Due S 18.68'
- 6' Poplar S 65° W 48.45'
- 6' Rail & Sign N 45° W 1.08'



Signed by John P. Goss

Date Aug. 5, 1996

Surveyor's Michigan License No. 23509

Fed. No. N-13

400