

**SURVEY &
REMONUMENTATION**

1993

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Gogebic
(County)

Located In:

Corner Code #

- | | | | | | |
|------------------------------------|---|------------|---|------------|------------|
| 1. Public Land Survey Section 15 | T | <u>49N</u> | R | <u>47W</u> | <u>T-6</u> |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| 2. Property Controlling in Section | S | _____ | T | _____ | R |
| | S | _____ | T | _____ | R |
| 3. Miscellaneous Property in Sec. | S | _____ | T | _____ | R |
| | S | _____ | T | _____ | R |

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

One-quarter corner S-15 & 14.

I, John R. Garske, in a field survey on December 7, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original survey by William Ives, Deputy Surveyor, on September 27, 1848. Set quarter post at 40chs (south to north) bearing trees:

- 10" sugar - S40°E - 16 links
- 5" sugar - N40°W - 16 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1 3/4" iron pipe with 2" cap set by Keweenaw Land Association which replaced a wood post found by Keweenaw Land Association. Corner position was noted to us by Pat Kamarainen, Forester with Keweenaw, as existing for over 40 years. An old blazed sugar maple bears N32°W, 9.40 feet with an old poster grown into the tree. I accepted this corner position as marking the original corner. No evidence of the original bearing trees could be found at this time.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced 1 3/4" iron pipe with 2" cap with a standard Bernsten 2 1/2" aluminum pipe 30" long with 3 1/2" aluminum cap stamped: County Remonumentation; T49N, R47W; 1/4 cor.; S-15; S-14; 1993; RLS 28410. Established the following bearing trees and reference objects:

- 10" sugar maple w/old blazes - N32°W - 9.40 feet
- 4" yellow birch - S60°E - 4.80 feet
- 3" sugar maple - N54°E - 7.65 feet
- 3" sugar maple - S23°W - 6.36 feet
- Steel sign post - west - 1.24 feet

Signed by John R. Garske
Surveyor's Michigan License No. 28410

Date 12/9/93

Register's Office } ss.
Gogebic County }

Received for record the
16TH day of DECEMBER
A. D. 1993 at 2:25 o'clock
P m., and recorded in
Liber 4 of CORNERS
on page 308.
Betty Lavin, Deputy
Register of Deeds

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

