

1993

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Gogebic
(County)

Located In:

Corner Code #

- 1. Public Land Survey Section 15 T 49N R 47W I-7
 T _____ R _____
 T _____ R _____
 T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

Section corner common to S-15, 14, 23 & 22.

May 29 93

I, John R. Garske, in a field survey on _____, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original survey by William Ives, Deputy Surveyor, on September 27, 1848. Set meander post with bearing trees:

- 10" hemlock - S43°E - 10 links
- 12" hemlock - N59°W - 15 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found stump mound with root holes with hemlock bark evident at 12" hemlock BT location. Found decayed remains at other hemlock BT location. Set monument in center of skid trail from decayed BT remains. Keweenaw Land Association said that an old post existed there many years ago but apparently destroyed as old trail runs through area.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set standard Bernsten 2 1/2" aluminum pipe with 3 1/2" aluminum cap stamped: T49N, R47W; S-15; S-14; S-22; S-23; 1993; RLS 28410. Established the following bearing trees and reference objects:

- 16" S. maple - N02°W - 10.28 feet
- 15" yellow birch - S71°E - 16.79 feet
- 4" S. maple - S29°E - 15.90 feet
- 15" S. maple - S60°W - 12.80 feet
- Steel sign post - east - 1.28 feet

Register's Office }
Gogebic County } ss.

Received, for Record the
16th day of DECEMBER
A. D. 1993 at 2:25 o'clock
P m., and recorded in
Liber 4 of COENERS
on page 309.
Betty Lassi Deputy
Register of Deeds

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Signed by John R Garske
Surveyor's Michigan License No. 28410

Date 12/9/93

