

SURVEY &
 MONUMENTATION
 MAY 18 1987
 COMMISSION

LAND CORNER RECORDATION CERTIFICATE Register's Office }
 Filing Requirement of Act 74, Mich. P.A. 1970 } Gogebic County } SS.

For corners in
Gogebic
 (County)
 Located in: _____ Corner Code # _____
 1. Public Land Survey T49NR 46W A-7
T49NR 47W M-7
 T ___ R ___
 T ___ R ___
 2. Property Controlling in Section S ___ T ___ R ___
 S ___ T ___ R ___
 3. Miscellaneous Property in Sec. S ___ T ___ R ___
 S ___ T ___ R ___
 4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____
 Sec. cor. comm. to sec's 18, 19, 13 & 24

Received for record the
16th day of AUGUST
 A. D. 1996 at 2:30 o'clock
P m., and recorded in
 Liber 6 of CORNERS
 on page 37
Richard J. Buxton
 Register of Deeds
 Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, John P. Goss, in a field survey on Aug. 23 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 Original corner established by William Burt in Sept. 1847. Set post.
 Original bearing trees: Yellow Birch 16"-S 28° W- 32 links; Hemlock 18"-N 62° E- 9 links; Hemlock 20"- N 55° E- 9 links; Hemlock 10"- S 30° E- 21 links.
 Richard Drahn on Sept. 19, 1991, restored corner position at recorded bearing and distance from remains of two (2) of the original bearing trees: He recorded said corner in Liber 4 on page 178. He set a 2½" dia. x 30" long split base aluminum monument with ¾" cap marked to show corner location; with the following witnesses: 16" Red Maple- N 08° W- 53.21'; 14" Hemlock - S 83° E- 31.67'; 7" Sugar Maple- S 28° W- 23.22'; 6' Metal sign rail- N 21° E- 2.6'.


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 I found the 2½" aluminum monument with ¾" cap set by Richard Drahn and it checked with his witnesses. I updated the corner monument and accessories as noted below to state and county specification.

Act 74 research on file.

Richard P. Drahn 9/12/96
 COUNTY

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 From the 2½" aluminum monument with ¾" aluminum cap stamped: T.49N., R. 46-47 W., S-18, S-19, S-13, S-24; 1991; R.L.S. 21564 & 28410.
 I established the following existing and new bearing trees and reference objects.

17" Red Maple	N 08° W	53.21'
15" Hemlock	S 83° E	31.67'
7" Sugar Maple	S 28° W	23.22'
9" Yellow Birch	N 60° E	20.52'
6' Metal sign & Rail	N 21° E	2.6'



Signed by John P. Goss
 Surveyor's Michigan License No. 23509

Date Aug. 23, 1996

Fed. No. N-1 & N-25