

**SURVEY &
REMONUMENTATION**

SEP 29 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

For corners in
Gogebic
(County)

Located In: Corner Code =#

- | | | |
|---------------------------------------|---------------------------|-------------|
| 1. Public Land Survey
<u>S-31</u> | T <u>49N</u> R <u>48W</u> | <u>C-12</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling
in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous
Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Received for record the
16TH day of SEPTEMBER
A. D. 1994 at 3:20 o'clock
P m., and recorded in
Liber 5 of CORNERS
on page 101

Ramona Collins, Deputy
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, John R. Garske, in a field survey on May 28, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original survey by William Ives, U.S.D.S., on August 8, 1848. Set wood post from which a 8" aspen - S43°E - 13 links; 5" cedar - N74°W - 14 links.

1932 plat - Supervisor's Plat No. 1 in Gov't. Lots 1 and 2, Section 31, T49N, R48W, Ironwood Township, Gogebic County, MI.

1990-1994 - Various surveys by John R. Garske, RLS 28410. Found 1" iron rod - Bearing trees or reference objects: P. Pole - N19°E - 63.10 feet; 9" R. maple - S85°W - 19.88 feet.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I found a 1" iron rod set in concrete at corner position as described as above protruding 17" above the ground. This location checks with found irons within Supervisor's Plat No. 1. I remonumented the corner position and upgraded accessories as noted below to state and county specifications.

Research on file with County Register of Deeds Office.

LEED GROUP

Approved


Richard P. Drabin

9/14/94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set a 2 1/2" x 17 1/2" flared aluminum pipe with 3 1/4" aluminum cap set in 6" x 12" cylinder and concrete over the found 1" iron rod. Aluminum cap is stamped: 1/4, T49N, R48W, S-31, S-32, 1994, RLS 28410. I established the following bearing trees and reference objects:

- Steel sign post - Due North - 1.65 feet
- Power pole - N19°E - 63.10 feet
- 9" R. maple - S85°W - 19.88 feet
- 5" R. maple - S36°W - 37.28 feet
- Centerline dirt road - Due East - 10.5 feet



Signed by John R. Garske

Date 8/31/94

Surveyor's Michigan License No. 28410