

**SURVEY &  
REMONUMENTATION**

OCT 0 8 1996

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in <u>Gogebic</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 49N R 48W	D-11
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register's Office }  
Gogebic County } sa.

Received for record the  
16<sup>th</sup> day of August  
A. D. 1996 at 11:15 o'clock  
A m., and recorded in  
Liber 6 of CORNERS  
page 22  
Ramona Collins, Deputy  
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_  
  
1/4 Corner 29&32, T49N, R48W.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, John R. Garske, in a field survey on May 16, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

- 1/4 post V7°-40°E  
Original Bearing Trees: Sugar 7"-N37°E-23 links  
DO 8"-S85°W-22 links.
- In 1984 J. Garske RLS 28410 reestablished and recorded corner, L2, pg. 587. Ties:  
P. pole - N55°W - 60.86 feet  
P. pole - S44°E - 41.79 feet  
S.E. Cor. Garage - N39°E - 37.06 feet

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

I found the P.K. nail just north of the centerline of Lake Road with the accessories noted above. I updated the corner to state and county specifications as noted below.

P.A. 74 Research on file.



**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

I replaced the P.K. nail with a 3" brass cap stamped: 1/4 T49N, R48W, S.32,S.29,1995, RLS 28410; cemented into the pavement from which I established the following reference objects:

- 2 1/2" Aluminum pipe with 3" aluminum cap stamped: County Remonumentation, R.M T49N, R48W, S.32, S29, 1995, RLS 28410, N25°W-32.42 with steel sign post 0.96'.
- P. pole - N55°W - 60.86 feet
- P. pole - S44°E - 41.79 feet
- S.E. Cor. Garage - N39°E - 37.06 feet

**PEER GROUP APPROVED**  
Richard L. D... 8/14/96  
**COUNTY REPRESENTATIVE**

Signed by John R. Garske Date 8-4-96  
Surveyor's Michigan License No. 28410